F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	537 R-1	COOK	245	8
STA. _____	TO STA. _____			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CONTRACT 62880

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY (100% STATE)	TRAFFIC SIGNALS US6/US45 (100% STATE)	TRAFFIC SIGNALS US45/158thPL. (100% VILLAGE)	TRAFFIC SIGNALS US6/94thAV. (95% STATE 5% VILLAGE)	INTER CONNECT (100% STATE)	SIGNAL PRE EMPTION (100% VILLAGE)	LIGHTING (100% VILLAGE)	WATER MAIN (100% VILLAGE)	SANITARY SEWER (100% VILLAGE)	VILLAGE LANDSCAPE (100% VILLAGE)	RETAINING WALL (100% VILLAGE)	NEW SIDEWALK (50% STATE 50% VILLAGE)
				CONSTRUCTION TYPE CODE											
				J000-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y030-1E	Y060	Y060	Y003	Y007	SFTY-1B
* 70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,310	2,310											
* 70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,790	1,790											
* 72000100	SIGN PANEL - TYPE 1	SQ FT	93		40	38	15								
* 72000200	SIGN PANEL - TYPE 2	SQ FT	120		120										
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	1,128	1,128											
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3,006	3,006											
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	19,396	19,396											
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	506	506											
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	34	34											
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	482	482											
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	396	396											
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	92	92											
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	11,890	11,890											
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1							1					
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1							1					
* 80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	137							137					
* 80800500	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	2							2					
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	5,236		937	562	209	3,498		30					
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	69		61		8								
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	101		53	20	28								
* 81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	13			13									
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	30		10	10	10								
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1,125		447	137	197	344							
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	4,324		624	491	484			2,725					
* 81400100	HANDHOLE	EACH	18		6	4	3	5							
* 81400200	HEAVY-DUTY HANDHOLE	EACH	9		4	4	1								

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)

SUMMARY OF QUANTITIES

SCALE: N/A DRAWN BY: BFH
DATE: 7-07-06 CHECKED BY: RCH

McDonough Associates Inc.
Engineers / Architects

8-1-06

I:\Dgn\sq01005.sht
7/31/2006
3:20:35 PM