

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	537 R-1	COOK	245	25

STORM AND SANITARY SEWER SCHEDULE

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

CONTRACT # 62880

DRAWING NUMBER	STRUCTURE	TO STRUCTURE	SS 1 RCP	SS 1 RCEP	SS 2 RCP	SS 2 RCP	SS 2 RCP	SS 2 RCP	SS 2 RCP	SS 2 RCP	SS RG CL	STORM SEW	STORM SEW	STORM SEW	STORM SEW	SAN SEW	SAN SEW	PIPE CULV	PIPE CULV	TRENCH
			CL 4 12	S38R24	CL 3 12	CL 3 15	CL 3 18	CL 3 21	CL 3 24	CL 3 30	A 2 30	D I 15	D I 12	D I 21	D I 24	8	10	TYPE 1 24	TYPE 2 24	BACKFILL
			FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	CU YD
DU-2	31R1	31L1			60															22
DU-2	31L2	31L1			6															2
DU-2	31L1	30L			44															1
DU-2	176R	177R			73															2
DU-2	177R	177L			104															38
DU-2	176L1	177L1																		
DU-2	177L	177L1											6					60		1
DU-2	177L1	178L1																	45	
DU-2	178L1	178L2																10		
DU-2	178L3	178L4			6															2
DU-2	178L4	178L5			6															2
DU-2	178L6	178L7			6															2
DU-2&3	178L7	179L			9															3
DU-2	178R1	178R2			6															2
DU-2	178R2	178R3			6															2
DU-2&3	178R3	179L			48															17
DU-3	179L2	179L	17																	6
DU-3	179L	179L1				40														15
DU-2&3	178L5	179L1			14															5
DU-3	179L1	180L1					124													47
DU-3	180R	EXCB	7																	3
DU-3	180L	EXCB			13															5
DU-3	180L1	181L									94									19
DU-3	181L	182L									80									15
DU-3	182L	EXCB/MH																9		
DU-3	182L	STUB									8									
DU-4	422L	422L1			15															5
DU-4	422R	422L1			70															25
DU-4	423L1	422L1								178										64
DU-4	423L	423L1			17															6
DU-4	423	423L1			32															12
DU-4	424R	423			40															14
DU-4	425L1	423L1								188										68
DU-4	425L	425L1			7															3
DU-4	426R	425L1			85															31
DU-4&5	427L1	425L1								188										68
DU-5	428R	427L1			80															29
DU-5	427L	427L1			3															1
DU-5	429L1	427L1								201										73
DU-5	429L	429L1			4															1
DU-5	429R2	429L1			54															20
DU-5	429	429R2			50															18
DU-5	429R	429R2			37															13
DU-5	432L	429L1									240									69
DU-5	432R	432L								107										41
DU-5	433R2	432R								93										
DU-5	433R	433R2			6															2
DU-5	167L3	433R2					70													
DU-5	167L1	167L3					27													
SUB-TOTAL2			24	0	901	40	221	0	382	755	240	0	6	0	124	0	0	0	0	776

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION US RTE 6 (159TH ST) AT US RTE 45 (LAGRANGE RD)
NAME	DATE	
		SCHEDULE OF QUANTITIES

SCALE: N/A
DATE: 12-05-09
DRAWN BY: JTF
CHECKED BY: RCH

McDonough Associates Inc.
Engineers / Architects