

R.F.L. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.2005-026	GRR	*	18	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\* WILL. KANE, DU PAGE AND COOK

CONTRACT 62960

### INDEX OF SHEETS

1. TITLE SHEET
2. INDEX OF SHEETS  
LIST OF APPLICABLE STATE STANDARDS  
GENERAL NOTES
3. SUMMARY OF QUANTITIES
4. COOK COUNTY LOCATION MAP
5. KANE COUNTY LOCATION MAP
6. DUPAGE COUNTY LOCATION MAP
7. WILL COUNTY LOCATION MAP
8. TYPICAL DETAILS FOR STEEL PLATE BEAM  
GUARDRAIL ANCHORAGE REPAIR
9. TYPICAL DETAIL FOR GUARDRAIL ANCHOR BLOCK REPAIR
10. TYPICAL DETAIL TO ANCHOR STEEL PLATE BEAM  
GUARDRAIL ON CONCRETE
11. DETAIL FOR CENTER LONGITUDINAL GUARDRAIL JOINT
12. DETAIL OF STEEL BEAM GUARDRAIL SPECIAL
13. DETAIL OF GUARDRAIL SUPPORT AND END ANCHORAGE
14. DETAIL OF THRIE-BEAM GUARDRAIL WITH MODIFIED OFFSET BLOCK
15. STEEL PLATE BEAM GUARDRAIL STEEL BLOCK-OUT DETAIL
16. CURB REMOVAL (PARTIAL) AND SHOULDER WIDENING  
FOR TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL
17. STEEL BRIDGE RAIL DETAIL
18. TRAFFIC CONTROL DETAIL FOR SHOULDER CLOSURE AND PARTIAL RAMP CLOSURE

### STATE STANDARDS

630001-06	701006-02	701411-03
630301-03	701011-01	701501-03
631006-03	701101-01	701606-04
631011-02	701201-02	701701-04
631026-02	701301-02	701801-03
631031-05	701400-02	702001-06
631036-04	701401-03	720011
635006-02	701406-04	BLR-23-1
635011-01		

### GENERAL NOTES

ALL WORK IS TO BE REPLACED IN KIND OR AS INDICATED ON THE CONTRACT QUANTITY SHEET.

GUARDRAIL WORK WILL INCLUDE ALIGNMENT AS NECESSARY TO RESTORE THE RAIL TO THE ORIGINAL CONDITIONS.

REMOVAL OF DAMAGED MATERIALS WILL INCLUDE DISMANTLING, LOADING, HAULING AND DISPOSAL. THE WORK SITE WILL BE LEFT IN A SAFE AND ORDERLY CONDITION.

NO MATERIAL SHOULD BE LEFT ON OR NEAR THE ROADWAY DURING NON-WORKING HOURS.

ANY NECESSARY TRAFFIC CONTROL WILL BE PROVIDED BY THE CONTRACTOR; APPROPRIATE STANDARDS ARE HEREWITH ATTACHED (SEE COVER SHEET).

THE LIMITS OF THE DAMAGED GUARDRAIL WILL BE MARKED WITH PAINT. THE REPLACEMENT PARTS AND THE QUANTITIES INDICATED ARE WITHIN THESE LIMITS AS MARKED.

REMOVED GUARDRAIL THAT IS NOT REPLACED ON THE SAME DAY MUST BE DELINEATED WITH LIGHTED BARRICADES. NO LOCATIONS WILL BE LEFT WITHOUT EITHER LIGHTED BARRICADES OR RESTORED GUARDRAIL AT ANY TIME.

GUARDRAIL MARKERS SHALL NOT BE ATTACHED TO TERMINAL SECTIONS.

REVISIONS	
NAME	DATE
CREATED	10-31-88

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, PLAN SHEETS  
AND STATE STANDARDS

SCALE: NONE  
DATE: 10-31-88

DRAWN BY R.F.L.  
CHECKED BY