

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	37-1HBR-1	HENRY	133	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BITUMINOUS SCHEDULE

PAY CODES:

31100100

X4073051

X4066414

48202400

48100100

STATIONING	REMARKS	LENGTH FEET	AVG. WIDTH FEET	MAINLINE AREA SQ. YD.	SHOULDER AREA SQ. YD.	SUBBASE GRANULAR MTL TYPE A				BIT. CONCRETE PAVEMENT SUPERPAVE FULL-DEPTH SQ. YD.	BIT. CONC. SURF CSE SP MIX C, N50 TON	BIT. SHOULDERS SP SQ. YDS	AGG. SHLDERS TYPE A TON
						4"	12"	15"	18"				
						TON	TON	TON	TON				
IL RTE. 26													
35 + 90 to 36 + 20	Poppy Garden Road LT	30	12.25	40.83	10.00					37.78		0	5
35 + 90 to 36 + 34	Poppy Garden Road RT	44	11.89	58.13	14.67					54.02		0	8
36 + 20 to 38 + 48	Poppy Garden Road LT	228	13.00	329.33	76.00					302.87		0	39
36 + 34 to 37 + 85	Poppy Garden Road RT	151	13.00	218.11	50.33					200.42		0	26
38 + 48 to 40 + 51	Poppy Garden Road LT	203	13.00	293.22	67.67		213.02	2.66		293.22		0	35
37 + 85 to 40 + 44	Poppy Garden Road RT	259	13.00	374.11	86.33		205.65	86.37		374.11		0	44
40 + 51 to 41 + 33	Poppy Garden Road LT	82	13.00	118.44	27.33		87.65			118.44		0	14
40 + 44 to 48 + 60	Poppy Garden Road RT	816	13.00	1178.67	272.00		867.27			1178.67		0	139
41 + 33 to 41 + 97	Poppy Garden Road LT	64	13.00	92.44	21.33		68.00			92.44		0	11
41 + 97 to 43 + 16	Poppy Garden Road LT	119	13.00	171.89	39.67		126.60			171.89		0	20
43 + 16 to 44 + 42	Poppy Garden Road RT	126	13.00	182.00	42.00		134.00			182.00		0	22
44 + 42 to 45 + 38	Poppy Garden Road LT	96	13.00	138.67	32.00		101.70			138.67		0	16
45 + 38 to 50 + 41	Poppy Garden Road LT	503	13.00	726.56	167.67		535.00			726.56	37.1	331	0
48 + 60 to 50 + 40.9	Poppy Garden Road RT	180.9	13.00	261.30	60.30		192.54			261.30	11.9	106	0
50 + 40.9 to 50 + 70.9	Approach Pavement West	30	26.00	86.67	10.00	29.0	0.00			86.67		0	0
52 + 76.9 to 53 + 6.9	Approach Pavement East	30	26.00	86.67	10.00	29.0	0.00			86.67		0	0
53 + 6.9 to 54 + 88	Poppy Garden Road LT	181.1	13.00	261.59	60.37		192.40			261.59	11.8	105	0
53 + 6.9 to 54 + 76	Poppy Garden Road RT	189.1	13.00	244.26	56.37		179.54			244.26	10.9	98	0
54 + 88 to 59 + 70.5	Poppy Garden Road LT	482.5	13.00	696.94	160.83		512.80			696.94		0	82
54 + 76 to 59 + 67.5	Poppy Garden Road RT	491.5	13.00	709.94	163.83		521.40			709.94		0	84
59 + 70.5 to 60 + 35	Poppy Garden Road LT	64.5	13.00	93.17	21.50		68.00			93.17		0	11
59 + 67.5 to 60 + 37	Poppy Garden Road RT	69.5	13.00	100.39	23.17		74.36			100.39		0	12
60 + 35 to 63 + 43	Poppy Garden Road LT	308	13.00	444.89	102.67		176.00		226.91	444.89		0	53
60 + 37 to 63 + 26	Poppy Garden Road RT	289	13.00	417.44	96.33		172.64			417.44		0	49
63 + 43 to 63 + 70	Poppy Garden Road LT	27	12.31	36.93	9.00					36.93		0	5
63 + 26 to 63 + 70	Poppy Garden Road RT	44	12.31	60.18	14.67				64.56	60.18		0	8
CARROLL STREET													
	GOOD NEIGHBOR POLICY -CTY RD 19	5280	22.00	645.35	3520							0	90
100 + 13 to 101 + 85	Carroll St LT (Stage I)	172	-	236.59	57.33						2.8	25	29
100 + 13 to 101 + 85	Carroll St RT (Stage II)	172	-	399.11	57.33						2.9	26	29
GRAND TOTAL				1281.05		58.0	4428.57	684.12	534.47	7422.85	77.4	691	831

PLOT DATE = Fri Sep 01 10:12:57 2006
 FILE NAME = c:\pcc\m\st\p2\3100\131006-rr.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = rnkawaj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY