

SCHEDULE OF QUANTITIES

CONTRACT NO. 64602

| | | | | |
|---------------------|-----------|---------------------------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 180 | 37-14RR-1 | HENRY | 133 | 17 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

42300300 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH

| SQ. YD. | LOCATION |
|---------|---------------------|
| 155 | STA. 39+75.46 PE-LT |
| 155 | TOTAL |

44000100 PAVEMENT REMOVAL

| SQ. YD. | LOCATION |
|---------|-----------------------|
| 1467 | STA. 35+90 TO 42+50 |
| 711 | STA. 60+50 TO 63+70 |
| 392 | STA. 100+13 TO 100+85 |
| 97 | STA. 101+13 TO 101+85 |
| 2667 | TOTAL |

PE-LT
CARROLL ST - STAGE I
CARROLL ST - STAGE II

44000700 APPROACH SLAB REMOVAL

| SQ. YD. | LOCATION |
|---------|---------------------|
| 88.9 | STA. 50+26 TO 50+66 |
| 88.9 | STA. 52+82 TO 53+22 |
| 178 | TOTAL |

44004300 PAVEMENT BREAKING

| SQ. YD. | LOCATION |
|---------|---------------------|
| 1725 | STA. 42+50 TO 50+26 |
| 1618 | STA. 53+22 TO 60+50 |
| 3343 | TOTAL |

44201709 CLASS D PATCHES, TYPE III, 5"

| SQ. YD. | LOCATION |
|---------|------------------------------------|
| 16.67 | STA. 101+48 7.5' WIDE - CARROLL ST |
| 16.67 | TOTAL |

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

| EACH | LOCATION |
|------|--|
| 1 | STA. 51+74.40 POPPY GARDEN ROAD BRIDGE OVER I-80 |
| 1 | TOTAL |

50100400 REMOVAL OF EXISTING STRUCTURES NO. 2

| EACH | LOCATION |
|------|---|
| 1 | STA. 461+11.67 36" GRATED END SECTION I-80 RT |
| 1 | TOTAL |

50100500 REMOVAL OF EXISTING STRUCTURES NO. 3

| EACH | LOCATION |
|------|--|
| 1 | STA. 462+25 36" GRATED END SECTION I-80 LT |
| 1 | TOTAL |

50102600 CONCRETE REMOVAL

| EACH | LOCATION |
|------|--|
| 1 | STA. 461+32 TO 461+66 I-80 CONCRETE PAD FOR SAND BARRELS |
| 1 | STA. 461+81 TO 462+15 I-80 CONCRETE PAD FOR SAND BARRELS |
| 2 | TOTAL |

50104400 CONCRETE HEADWALL REMOVAL

| EACH | LOCATION |
|------|----------------------------|
| 1 | STA. 461+26.25 85' LT I-80 |
| 1 | STA. 462+35.46 93' RT I-80 |
| 2 | STA. 60+59 LT & RT |
| 4 | TOTAL |

50105210 REMOVE EXISTING CULVERTS

| FOOT | LOCATION |
|------|-------------------------------------|
| 73 | STA. 60+58.59 30" CMP - AR CULVERT |
| 87 | STA. 100+41.28 30" CMP - AR CULVERT |
| 124 | STA. 461+12 TO 462+36 36" I-80 RT |
| 100 | STA. 461+26 TO 462+26 36" I-80 LT |
| 384 | TOTAL |

542A1075 PIPE CULVERTS, CLASS A, TYPE 2 30"

| FOOT | LOCATION |
|------|--------------------------|
| 82 | STA. 60+58.59 AR CULVERT |
| 82 | TOTAL |

542A1915 PIPE CULVERTS, CLASS A, TYPE 3 30"

| FOOT | LOCATION |
|------|-----------------------|
| 106 | STA. 46+00 AR CULVERT |
| 106 | TOTAL |

542A4021 PIPE CULVERTS, CLASS A, TYPE 6 36"

| FOOT | LOCATION |
|------|-------------------------------|
| 182 | STA. 461+08 TO 462+90 I-80 RT |
| 180 | STA. 460+85 TO 462+65 I-80 LT |
| 362 | TOTAL |

542C1075 PIPE CULVERTS, CLASS C, TYPE 2 30"

| FOOT | LOCATION |
|------|--------------------------------------|
| 10 | STA. 100+41.28 CARROLL ST. - STAGE I |
| 75 | STA. 100+41.28 CARROLL ST. |
| 85 | TOTAL |

Plot Date = Mon Oct 02 09:54:19 2006
File Name = 50100500.dgn
Plot Scale = 50.00000 / IN.
User Name = reneka.j

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. DATE
HORIZ. DATE

DRAWN BY
CHECKED BY

SCHEDULE OF QUANTITIES