CONTRACT NO. 64602

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	37-1HBR-1	HENRY	133	21
STA. _____ TO STA. _____				
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION					
21	STA. 100+13	TO 102+40		CL	YELLOW SKIP DASH	STAGE I - CARROLL ST
21	STA. 100+13	TO 102+40		CL	YELLOW SKIP DASH	STAGE II - CARROLL ST
42 TOTAL						

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION					
860	STA. 35+90	TO 44+50		LTEOP	SOLID WHITE	
860	STA. 35+90	TO 44+50		RTEOP	SOLID WHITE	
215	STA. 35+90	TO 44+50		CL	YELLOW SKIP DASH	
621	STA. 44+50.0	TO 50+70.90		LTEOP	SOLID WHITE	
621	STA. 44+50.0	TO 50+70.90		RTEOP	SOLID WHITE	
1093	STA. 52+76.90	TO 63+70		RTEOP	SOLID WHITE	
1093	STA. 52+76.90	TO 63+70		RTEOP	SOLID WHITE	
137.5	STA. 44+50.0	TO 50+00		CL	YELLOW SKIP DASH	
137.5	STA. 44+50.0	TO 50+00		CL	SOLID YELLOW	
600	STA. 50+00	TO 53+00		CL	SOLID DBL YELLOW	
990	STA. 53+00	TO 63+10		CL	SOLID YELLOW	
247.5	STA. 53+00	TO 63+10		CL	YELLOW SKIP DASH	
15	STA. 63+10	TO 63+70		CL	YELLOW SKIP DASH	
195	STA. 43+16	TO 101+85		LTEOP	SOLID WHITE	STAGE III - CARROLL ST
175	STA. 100+10.0	TO 101+85		CL	SOLID DBL YELLOW	STAGE III - CARROLL ST
195	STA. 44+42	TO 101+85		RTEOP	SOLID WHITE	STAGE III - CARROLL ST
8056 TOTAL						

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION					
1750	STA. 446+00	TO 463+00		RTEOP	SOLID WHITE	I-80 STAGE II
1800	STA. 460+00	TO 478+00		RTEOP	SOLID WHITE	I-80-STAGE II
3550 TOTAL						

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION					
286.67	STA. 35+90	TO 44+50		LTEOP	SOLID WHITE	
286.67	STA. 35+90	TO 44+50		RTEOP	SOLID WHITE	
71.67	STA. 35+90	TO 44+50		CL	YELLOW SKIP DASH	
204.93	STA. 44+50.0	TO 50+70.90		LTEOP	SOLID WHITE	
204.93	STA. 44+50.0	TO 50+70.90		RTEOP	SOLID WHITE	
360.69	STA. 52+76.90	TO 63+70		RTEOP	SOLID WHITE	
360.69	STA. 52+76.90	TO 63+70		RTEOP	SOLID WHITE	
45.38	STA. 44+50.0	TO 50+00	LT	CL	YELLOW SKIP DASH	
45.38	STA. 44+50.0	TO 50+00	RT	CL	SOLID YELLOW	
198	STA. 50+00	TO 53+00		CL	SOLID DBL YELLOW	
326.7	STA. 53+00	TO 63+10	LT	CL	SOLID YELLOW	
81.68	STA. 53+00	TO 63+10	RT	CL	YELLOW SKIP DASH	
5	STA. 63+10	TO 63+70		CL	YELLOW SKIP DASH	
7	STA. 100+13	TO 102+40		CL	YELLOW SKIP DASH	STAGE III - CARROLL ST
578	STA. 446+00	TO 463+50		RTEOP	SOLID WHITE	I-80 STAGE II
594	STA. 460+00	TO 478+00		RTEOP	SOLID WHITE	I-80-STAGE II
3657 TOTAL						

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
400	STA. 460+50	TO 464+50		STAGE I	I-80 WB-INSIDE LN
400	STA. 446+00	TO 463+00		STAGE I	I-80 EB-INSIDE LN
800 TOTAL					

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
450	STA. 460+00	TO 464+50		STAGE II	I-80 WB-OUTSIDE LANE
350	STA. 459+50	TO 463+00		STAGE II	I-80 EB-OUTSIDE LANE
800 TOTAL					

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION				
652	STA. 35+90	TO 43+16		LTEOP	SOLID WHITE
1258	STA. 44+42	TO 50+70.90		LTEOP	SOLID WHITE
2186	STA. 52+76.90	TO 63+70		LTEOP	SOLID WHITE
2962	STA. 35+90	TO 50+70.90		RTEOP	SOLID WHITE
2186	STA. 52+76.90	TO 63+70		RTEOP	SOLID WHITE
255	STA. 35+90	TO 41+00		CL	YELLOW SKIP DASH
450	STA. 41+00	TO 50+00	LT	CL	YELLOW SKIP DASH
1800	STA. 41+00	TO 50+00	RT	CL	SOLID YELLOW
1200	STA. 50+00	TO 53+00		CL	SOLID DBL YELLOW
2020	STA. 53+00	TO 63+10	LT	CL	SOLID YELLOW
505	STA. 53+00	TO 63+10	RT	CL	YELLOW SKIP DASH
300	STA. 63+10	TO 63+70		CL	YELLOW SKIP DASH
412	STA. 43+16	TO 101+85		LTEOP	SOLID WHITE
300	STA. 100+13	TO 101+85		CL	SOLID DBL YELLOW
402	STA. 100+13	TO 101+85		RTEOP	SOLID WHITE
16888 TOTAL					

78001180 PAINT PAVEMENT MARKING - LINE 24"

FOOT	LOCATION		
24	STA. 100+20	CARROLL ST.	(WHITE STOP BAR)
24 TOTAL			

78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)

EACH	LOCATION
1	STA. 51+00.0
1	STA. 51+80.0
1	STA. 52+60.0
3 TOTAL	

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION			
7	STA. 45+50	TO 50+70.90	LT	MONODIRECTIONAL SILVER
4	STA. 48+51.50	TO 50+70.90	RT	MONODIRECTIONAL SILVER
4	STA. 52+77.50	TO 54+96.25	LT	MONODIRECTIONAL SILVER
4	STA. 52+77.50	TO 54+96.25	RT	MONODIRECTIONAL SILVER
19 TOTAL				

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Mon Oct 02 09:26:17 2006
FILE NAME = c:\pw_jle14\d2310\d1310scrr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = renkesj

SCHEDULE OF QUANTITIES