CONTRACT NO. 64626

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37RS-6	OGLE	69	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	I000 QUANTITY 80%FED 20%STATE	Y025 QUANTITY 50%CITY 50%STATE	SFTY-1B QUANTITY 100%CITY	Y031-1F QUANTITY 80%FED 20%STATE
20101700	SUPPLEMENTAL WATERING	UNIT	80	80			
20800150	TRENCH BACKFILL	CU YD	5			5	
25200100	SODDING	SQ YD	591	2		589	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11.6	9.9	1.7		
40600300	AGGREGATE (PRIME COAT)	TON	29	25	4		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600990	TEMPORARY RAMP	SQ YD	972	972			
40602000	BITUMINOUS REPLACEMENT OVER PATCHES SUPERPAVE	TON	34	34			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6641	2211		4430	
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	1268			1268	
42400800	DETECTABLE WARNINGS	SQ FT	67	67			
44000100	PAVEMENT REMOVAL	SQ YD	178	178			
44000600	SIDEWALK REMOVAL	SQ FT	8731	2789		5942	
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	93	93			
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	103	103			
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	473	473			
44213100	PAVEMENT FABRIC	SQ YD	577	577			
44213200	SAW CUTS	FOOT	2044	2044			
* 56400300	FIRE HYDRANT TO BE ADJUSTED	EACH	1	1			
60242400	INLETS, SPECIAL	EACH	1			1	
60255500	MANHOLES TO BE ADJUSTED	EACH	25	11		14	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	I000 QUANTITY 80%FED 20%STATE	Y025 QUANTITY 50%CITY 50%STATE	SFTY-1B QUANTITY 100%CITY	Y031-1F QUANTITY 80%FED 20%STATE
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	5			
60260100	INLETS TO BE ADJUSTED	EACH	4	4			
60500060	REMOVING INLETS	EACH	1			1	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	694	694			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	8			
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	1970	1970			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	169	169			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	295	295			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3190	3190			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1260	1260			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1733	1733			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	738	738			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	174	174			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	62	62			
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	35				35
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	35				35

* SPECIALTY ITEM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

SUMMARY OF QUANTITIES

PLOT DATE = Wed Aug 09 14:56:05 2006
FILE NAME = e:\pwidata\ogle\d1648\summ.dgn
PLOT SCALE = 192.8908 ' / in.
USER NAME = raymarl