

CONTRACT NO. 64897

PAVING SCHEDULE

STATION TO STATION	AGGREGATE BASE COURSE, TYPE A, 12" (35101100)	AGGREGATE BASE COURSE, TYPE B 8" (35102000)	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH (X3560130)	INCIDENTAL BITUMINOUS SURFACING (40800040)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 (X4066414)	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50 (X4066765)
	SQ YD			TON		
US 52/IL 64						
1432+00.60 TO 1434+40.60			146.7		73.2	113.7
1434+40.60 TO 1441+89.27			457.6		215.0	507.7
1441+89.27 TO 1444+29.27			146.7		73.2	92.8
STAGE CONSTRUCTION						
1440+49.00 TO 1441+61.00			107.4			
WILLOW ROAD						
FIELD ENTRANCE AT 102+51.70						
101+75.26 TO 103+00.49	656.7			105.5		
103+27.80 TO 104+58.46	713.2			114.3		
104+58.46 TO 105+20.00	150.4			32.5		
TOTAL	1520.3	64.5	858.4	252.3	361.4	714.1
USE	1,521	65	859	253	362	715

40600980: BITUMINOUS SURFACE REMOVAL - BUTT JOINT

STATION TO STATION	WIDTH	LENGTH	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	
	FOOT			SQ YD
FAP 17 (US 52/IL 64)				
1432+00.60	1432+30.60	24.9	30.0	83.0
1443+99.27	1444+29.27	25.3	30.0	84.3
TOTAL				167.3
USE				168

40600990: TEMPORARY RAMP

STATION TO STATION	WIDTH	AREA	
	FOOT	SQ YD	
FAP 17 (US 52/IL 64)			
1432+00.60	1432+05.60	24.9	13.8
1444+24.27	1444+29.27	25.3	14.1
TOTAL			27.9
USE			28

44000100: PAVEMENT REMOVAL

STATION TO STATION	SIDE	AREA	
		RT	SQ YD
1440+20.0	1440+77.9	RT	22.5
1440+77.9	1441+58.0	RT	62.3
1441+58.0	1442+16.0	RT	22.6
TOTAL			107.4
USE			108

44001430: BITUMINOUS SHOULDER REMOVAL

STATION TO STATION	SIDE	SHOULDER REMOVAL	
		RT	SQ YD
1432+00.60	1436+92.75	LT & RT	164.1
1436+92.75	1437+04.42	LT	2.0
1437+34.65	1437+53.24	RT	3.1
1437+53.24	1444+29.27	LT & RT	225.4
TOTAL			394.6
USE			395

CLASS D PATCHES, 12 INCH

STATION	CLASS D PATCHES	
	TY II (44201789)	TY III (44201794)
	SQ YD	
1441+42.0		37.4
1441+73.9	23.7	
TOTAL	23.7	37.4
USE	24	38

44300200: STRIP REFLECTIVE CRACK CONTROL

STATION TO STATION	SIDE	LENGTH	
		FT	TON
FAP 17 (US 52/IL 64)			
1432+00.60	1444+29.27	LT	1228.7
1432+00.60	1444+29.27	RT	1228.7
TOTAL			2457.4
USE			2458

48101200: AGGREGATE SHOULDERS, TYPE B

STATION TO STATION	SIDE	WIDTH	AGGREGATE SHOULDERS, TYPE B
		FT	TON
US 52/IL 64			
1432+00.60 TO 1436+24.32	LT	1	42.9
1432+00.60 TO 1436+50.32	RT	1	45.5
1438+04.57 TO 1444+29.27	LT	1	63.2
1438+05.66 TO 1444+29.27	RT	1	63.1
WILLOW ROAD			
104+58.46 TO 105+20.00	LT/RT	2	12.5
TOTAL			227.2
USE			228

48202410: BITUMINOUS SHOULDERS, SUPERPAVE 6 1/2"

STATION TO STATION	SIDE	WIDTH	BITUMINOUS SHOULDERS, SUPERPAVE 6 1/2"
		FT	SQ YD
US 52/IL 64			
1432+00.60 TO 1436+24.32	LT	3	141.2
1432+00.60 TO 1436+50.32	RT	3	149.9
1438+04.57 TO 1444+29.27	LT	3	208.2
1438+05.66 TO 1444+29.27	RT	3	207.9
TOTAL			707.3
USE			708

REMOVAL OF EXISTING STRUCTURES

STATION	STRUCTURE NUMBER	STRUCTURE TYPE	REMOVAL OF EXISTING STRUCTURES (50100300) (50100400)
			EACH
WILLOW ROAD			
103+39.11	1	2'x2' BOX	1
102+90.78	2	2'x1.5' BOX	1
TOTAL			2

PIPE CULVERT SCHEDULE

STATION	SIDE	TYPE	STANDARD	CLASS A	CLASS D			END SECTIONS		CORRUGATED STEEL PIPE MULTIPLE END SECTIONS DOUBLE 30" (#2001376)	CULVERT DROP BOX (X0322263)	GRATED CULVERT EXTENSION, NO 1 (Z0029001)
				TYPE 2	TYPE 1	TYPE 2	15"	30"				
				48" (542A1093)	15" (542D0220)	30" (542D0235)	42" (TEMPORARY) (5422D042)	15" (54213450)	30" (54213465)			
				FOOT					EACH			
FAP ROUTE 17 (US 52/IL 64)												
1441+42.0	CL	PIPE CULVERT & END SECTION	542206	96							1	1
1441+73.9	RT	PIPE CULVERT (TEMPORARY)					16					
WILLOW ROAD												
102+51.7	RT	PIPE CULVERT & END SECTIONS	542401		30			2				
102+66.0	CL	PIPE CULVERT & END SECTIONS	542401			148				2		
103+63.5	CL	PIPE CULVERT & END SECTIONS	542401			84			2			
TOTALS				96	30	232	16	2	2	2	1	1
USE				96	30	232	16	2	2	2	1	1

CONTINGENCY ITEMS FOR FIELD TILE REPAIR AND REPLACEMENT

ITEM	UNIT	QUANTITY
EXPLORATION TRENCH 52" DEPTH (61100500)	FOOT	200
MISCELLANEOUS CONCRETE (61100605)	CU YD	3
STORM SEWERS PROTECTED, CLASS A, 12" (61101013)	FOOT	220
STORM SEWERS PROTECTED, CLASS A, 15" (61101017)	FOOT	100
FIELD TILE JUNCTION VAULTS, 2' DIA (61133100)	EACH	4
FIELD TILE JUNCTION VAULTS, 3' DIA (61133200)	EACH	1

63500105: DELINEATORS

STATION TO STATION	SIDE	DELINEATORS	
		RT	EACH
1433+74.60	1442+55.27	LT	7
	1441+59.72	LT	1
1433+74.60	1442+55.27	RT	8
	1441+24.75	RT	1
TOTAL			17

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 17
SCHEDULES OF QUANTITIES

DRAWN BY TJD
CHECKED BY AWM
DATE 8/22/2006