

66600105: FURNISHING AND ERECTING RIGHT OF WAY MARKERS

| STATION | SIDE | OFFSET | EACH |
|----------------------|------|--------|------|
| | | FEET | |
| FAP 17 (US 52/IL 64) | | | |
| 1431+50.00 | LT | 33.00 | 1 |
| 1431+50.00 | RT | 33.00 | 1 |
| 1432+00.00 | RT | 60.00 | 1 |
| 1433+00.00 | LT | 45.00 | 1 |
| 1433+74.60 | RT | 60.00 | 1 |
| 1434+50.26 | LT | 50.00 | 1 |
| 1434+00.86 | RT | 65.00 | 1 |
| 1436+00.00 | RT | 65.00 | 1 |
| 1436+44.00 | RT | 70.00 | 1 |
| 1436+50.37 | LT | 60.00 | 1 |
| 1436+80.18 | LT | 70.00 | 1 |
| 1437+53.46 | RT | 65.00 | 1 |
| 1437+95.45 | LT | 50.00 | 1 |
| 1438+00.00 | RT | 55.00 | 1 |
| 1439+00.00 | LT | 55.00 | 1 |
| 1439+00.00 | RT | 55.00 | 1 |
| 1440+00.00 | RT | 55.00 | 1 |
| 1440+00.00 | LT | 60.00 | 1 |
| 1441+00.00 | LT | 60.00 | 1 |
| 1441+00.00 | RT | 65.00 | 1 |
| 1442+00.00 | LT | 60.00 | 1 |
| 1442+55.27 | LT | 33.00 | 1 |
| 1444+00.00 | RT | 55.00 | 1 |
| 1445+00.00 | LT | 33.00 | 1 |
| 1446+00.00 | LT | 45.00 | 1 |
| 1446+50.00 | RT | 80.00 | 1 |
| 1447+00.00 | LT | 45.00 | 1 |
| 1448+00.00 | LT | 33.00 | 1 |
| 1448+02.93 | RT | 80.00 | 1 |
| WILLOW ROAD | | | |
| 101+65.00 | LT | 25.00 | 1 |
| 101+65.00 | RT | 25.00 | 1 |
| 105+00.00 | LT | 25.00 | 1 |
| 105+20.00 | RT | 25.00 | 1 |
| TOTAL | | | 33 |

66700305: PERMANENT SURVEY MARKERS, TYPE II

| STATION | DESCRIPTION | PERMANENT SURVEY MARKERS TYPE II |
|----------------------|-------------|----------------------------------|
| | | EACH |
| FAP 17 (US 52/IL 64) | | |
| 1433+74.60 | PC | 1 |
| 1442+55.27 | PT | 1 |
| TOTAL | | 2 |

SHORT-TERM PAVEMENT MARKING AND REMOVAL SCHEDULE

| STATION TO STATION | SIDE | SHORT-TERM PAVEMENT MARKING (70300100) | WORK ZONE PAVEMENT MARKING REMOVAL (70301000) | |
|------------------------|------------|--|---|------|
| | | FOOT | SQ FT | |
| FAP 17 (US 52/IL 64) | | | | |
| LEVELING BINDER COURSE | | | | |
| 1432+00.60 | 1444+29.27 | CL | 122.9 | |
| SURFACE COURSE | | | | |
| 1432+00.60 | 1444+29.27 | CL | 122.9 | 41.0 |
| TOTAL | | | 245.8 | 41.0 |
| USE | | | 246 | 41 |

| | | | | |
|----------------|--------------|----------------|-----------------|--------------|
| F.A.P. RTE. 17 | SECTION 16-T | COUNTY CARROLL | TOTAL SHEETS 47 | SHEET NO. 10 |
|----------------|--------------|----------------|-----------------|--------------|

CONTRACT NO. 64897

PAVEMENT MARKING SCHEDULE

| STATION TO STATION | SIDE | PAINT PAVEMENT MARKING (78001110) | | | RAISED REFLECTIVE PAVEMENT MARKER (78100100) |
|----------------------|------------|-----------------------------------|--------------------------|---------------------------|--|
| | | LINE 4" WHITE EDGE LINE | LINE 4" YELLOW SKIP-DASH | LINE 4" YELLOW SOLID LINE | |
| | | FOOT | | | EACH |
| FAP 17 (US 52/IL 64) | | | | | |
| 1432+00.60 | 1436+24.32 | LT | 423.7 | | |
| 1432+00.60 | 1436+50.32 | RT | 449.7 | | |
| 1432+00.60 | 1438+30.00 | CL | | 157.4 | |
| 1432+00.60 | 1438+30.00 | CL* | | | 8 |
| 1438+04.57 | 1444+29.27 | LT | 624.7 | | |
| 1438+05.66 | 1444+29.27 | RT | 623.6 | | |
| 1438+30.00 | 1444+29.27 | CL | | 149.8 | 8 |
| WILLOW ROAD | | | | | |
| 101+75.84 | 102+81.40 | LT | 137.3 | | |
| 101+75.84 | 103+30.00 | RT | 190.1 | | |
| 103+00.70 | 105+20.0 | LT | 270.3 | | |
| 103+53.70 | 105+20.00 | RT | 203.5 | | |
| TOTAL | | | 2923.0 | 307.2 | 629.4 |
| 1ST APPLICATION | | | | 3860 | |
| 2ND APPLICATION | | | | 3860 | |
| USE | | | | 7720 | 16 |

* NORTHBOUND NO PASSING ZONE

78300200: RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

| STATION TO STATION | SIDE | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | |
|----------------------|------------|---|----|
| | | EACH | |
| FAP 17 (US 52/IL 64) | | | |
| 1432+00.60 | 1444+29.27 | CL | 16 |
| TOTAL | | | 16 |

A2007814: TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED

| LOCATION | TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED |
|---------------------------------|--|
| | EACH |
| SEE POLICY GUIDELINES - SHEET 3 | |
| | 2 |
| TOTAL | 2 |

X0950100: PIPE CULVERT REMOVAL, 15"

| STATION | SIDE | PIPE CULVERT REMOVAL, 15" |
|-----------|------|---------------------------|
| | | FOOT |
| 1435+25.0 | LT | 10 |
| TOTAL | | 10 |

X4420500: TEMPORARY PAVEMENT PATCH

| STATION | TEMPORARY PAVEMENT PATCH |
|-----------|--------------------------|
| | SQ YD |
| 1441+42.0 | 38 |
| 1441+73.9 | 23.7 |
| TOTAL | 61.7 |
| USE | 62 |

Z0020900: ESTABLISHING AND REFERENCING LAND SECTION MARKERS

| LOCATION | STATION | SIDE | OFFSET | ESTABLISHING AND REFERENCING LAND SECTION MARKERS |
|-----------------------|------------|------|--------|---|
| | | | | EACH |
| NW CORNER, SECTION 21 | 1437+00.48 | RT | 70.54' | 1 |
| TOTAL | | | | 1 |

Z0023600: FILLING EXISTING CULVERTS

| STATION | FILLING EXISTING CULVERTS |
|------------|---------------------------|
| | EACH |
| 1435+25.00 | 1 |
| 1441+73.93 | 1 |
| TOTAL | 2 |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 17 SCHEDULES OF QUANTITIES

DATE 8/22/2006

DRAWN BY TJD
CHECKED BY AWM