

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	U-BR	LA SALLE	38	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

AC
F

AC
BRF

← 80% FED 20% STATE →

SUMMARY OF QUANTITIES		UNIT	TOTAL QNTY	I000	CONSTRUCTION TYPE CODE	
CODE NO	ITEM				X080-2A	
51201610	FURNISHING STEEL PILES HP12X63	FOOT	96	0	96	
51500100	NAME PLATES	EACH	1	0	1	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	37	0	37	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	191	0	191	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	612.5	612.5	0	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	0	
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	4	4	0	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	874	874	0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	0	
67100100	MOBILIZATION	L SUM	1	1	0	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	0	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	0	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	0	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	0	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	0	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	0	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	180	180	0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	793	793	0	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	625	625	0	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	475	475	0	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2009	2009	0	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	251	251	0	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9	0	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10	0	
78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2	0	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	0	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	796	796	0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9	0	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	240	0	240	
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	533	533	0	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	173	173	0	
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	359	359	0	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	167	167	0	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	0	1	
Z0002600	BAR SPLICERS	EACH	170	0	170	
Z0002000	FILTER FABRIC	SQ YD	234	0	234	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	4	0	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	0	
Z0065000	SETTING PILES IN ROCK	EACH	18	0	18	

*
*
*

*
*
*

△
△

* SPECIALTY ITEM
△ SFTY-3N

PLOT DATE = 05/20/2006
FILE NAME = \\s\8\sumner\of\quantities.dgn
PLOT SCALE = 50.0000 / 1
USER NAME = DFC

COOMBE-BLOXDORF P.C.
Engineers / Land Surveyors
Springfield, Illinois
Design Firm License No. 184-002703

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 71 OVER UNNAMED STREAM
FAP RT 67, SECTION U-BR
LA SALLE COUNTY

SCALE: DATE: 01/13/06

DRAWN BY: CHECKED BY: