

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
627	U-BR	La SALLE	38	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STATION	PAVEMENT REMOVAL LENGTH	PAVEMENT REMOVAL
	FT	SQ YD
STA 97+82.04 TO STA 98+33.75	51.71	138
STA 98+94.05 TO STA 99+35.76	41.71	111
TOTAL		249

LOCATION STA TO STA	WIDTH	BR APPR PVT
	FT	SQ. YD
STA 97+88.04 TO STA 98+18.04	32	106.67
STA 98+99.76 TO STA 99+29.76	32	106.67
TOTAL		213.00

APPROX. LOCATION	WIDTH	STREET NAME	TEMP RAMP
			SQ. YD
94+35.81	24	BEGINNING OF JOB	13.33
97+82.04	24	STR. OMISSION STAGE I	32.00
99+35.76	24	STR. OMISSION STAGE I	32.00
97+82.04	24	STR. OMISSION STAGE II	32.00
99+35.76	24	STR. OMISSION STAGE II	32.00
97+82.04	24	STR. OMISSION RESURFACING	13.33
99+35.76	24	STR. OMISSION RESURFACING	13.33
103+21.29	24	END OF JOB	13.33
97+28.63	40	PE STA 97+28.63	22.22
TOTAL			204.00

STATION	TBT	SPBGR	TBT	G/R MKR	TERM MKR
	TY 6	TY A	TY 1	TY A	DIR. APP.
	EACH	FOOT	EACH	EACH	EACH
LT STA 89+79.17 TO STA 90+29.17			1		1
LT STA 93+65.41 TO STA 97+77.91		412.5		5	
LT STA 97+77.91 TO STA 98+08.56	1				
LT STA 98+90.28 TO STA 99+20.93	1				
LT STA 99+20.93 TO STA 100+20.93		100		2	
LT STA 100+20.93 TO STA 100+70.93			1		1
RT STA 97+46.87 TO STA 97+96.87			1		1
RT STA 97+96.87 TO STA 98+27.51	1			1	
RT STA 99+09.24 TO STA 99+39.89	1				
RT STA 99+39.89 TO STA 100+39.89		100		2	
RT STA 100+39.89 TO STA 100+89.89			1		1
TOTALS	4	612.5	4	10	4

LOCATION STA TO STA	WIDTH	FLEX PVT CONN
	FT	SQ. YD
STA 97+82.04 TO STA 97+88.04	32	21.33
STA 99+29.76 TO STA 99+35.76	32	21.33
TOTAL		43.00

LOCATION (STATION)	DIAMETER 6-15 (UNITS)	DIAMETER OVER 15 (UNITS)
LT STA 97+24	6	
LT STA 97+31	6	
LT STA 97+48.5	7	
LT STA 97+49	7	
LT STA 97+49.5	7	
LT STA 97+97		18
TOTAL	33	18

LOCATION	PERIMETER EROSION BARRIER	TEMPORARY DITCH CHECKS	TEMPORARY FENCE
	FT	EA	FT
RT STA 93+00 TO STA 96+50, 36' RT	350		350
ADDITIONAL CONTINGENCY QTY	200	8	
TOTAL	550	8	350

STATION	SPBGR REM
	FT
LT STA 89+79.17 TO STA 90+29.17	50
LT STA 93+64.98 TO STA 98+20.94	455.96
RT STA 97+44.98 TO STA 98+46.54	101.56
LT STA 98+80.73 TO STA 100+44.94	164.21
RT STA 99+07.00 TO STA 100+09.35	102.35
TOTAL	874.08

LOCATION STATION TO STATION	LENGTH (FT)	REMOVAL (SQ FT)
CENTERLINE (6") STA 93+52.30 TO STA 103+56.59	1004.29	125.54
EDGE LINES (4") STA 93+52.30 TO STA 103+56.59	1004.29	670
TOTAL		796

STATION ON PARAPET	BARR MKR, TY B EACH
LT STA 98+49.66	1
RT STA 98+68.14	1
TOTAL	2

LOCATION STATION TO STATION (FROM STOP BAR TO STOP BAR)	LENGTH	6" YELLOW SKIP-DASH	4" WHITE SOLID
		(FT)	(FT)
IL 71 STA 93+52.30 TO 103+56.59	1004.29	251.1	2008.6
TOTAL	1004.3	251	2009

LOCATION STATION TO STATION	RAISED REFL. REM	RAISED REFL. BI-DIR YELLOW
	(EACH)	(EACH)
STA. 94+35.81 TO STA. 97+82.04	4	4
STA. 99+35.76 TO STA 103+21.29	5	5
TOTAL	9	9

LOCATION STATION TO STATION	LENGTH	SHORT TERM (FT)
4' SKIP-DASH CENTERLINE STA 93+52.30 TO STA 103+56.59	1004.29	100
SHORT-TERM EDGE LINES STA 93+52.30 TO STA 103+56.59	1004.29	80
TOTAL		180

LOCATION STATION TO STATION	LENGTH (FT)	REMOVAL (SQ FT)
STOP BAR STA 93+52.30		24
STOP BAR STA 103+56.59		24
STOP BAR PE STA 97+82.04		15.3
TEMPORARY EDGE LINES STA 93+52.30 TO 103+56.59 STAGE I	1004.29	335
TEMPORARY EDGE LINES STA 93+52.30 TO 103+56.59 STAGE II	1004.29	335
SHORT-TERM EDGE LINES STA 93+52.30 TO 103+56.59 PRIOR TO SURF CSE	1004.29	26.84
SHORT-TERM SKIP-DASH STA 93+52.30 TO 103+56.59 PRIOR TO SURF CSE	1004.29	33.33
TOTAL		793

COOMBE-BLOXDORF P.C.
Engineers / Land Surveyors
Springfield, Illinois
Design Firm License No. 184-002703

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL ROUTE 71 OVER UNNAMED STREAM
FAP RT 627, SECTION U-BR
LA SALLE COUNTY

SCALE: DATE: 01/13/06
DRAWN BY: CHECKED BY: