

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-4B)BR	LASALLE	365	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	CONSTRUCTION CODE TYPE: ITEM		URBAN			
			80% FED 20% STATE TOTAL	J000 RDWY	Y030-1E LIGHTING	X971-5B BRIDGE
* X0322763	FURNISH AND INSTALL PAVEMENT SENSORS	EACH	2	2		
X0325598	DRAINAGE SCUPPERS, DS-12M10	EACH	36			36
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	63			63
* X0323898	CLOSED CIRCUIT TELEVISION DOME CAMERA	EACH	2	2		
* X0323904	ILLINOIS DEPARTMENT OF TRANSPORTATION COMMUNICATIONS NODE	L SUM	1	1		
* X0323913	FIBER OPTIC LINK (CLOSED CIRCUIT TELEVISION)	EACH	2	2		
* X0323917	CABINET, MODEL 334	EACH	1	1		
* X0323921	POLE MOUNTED EQUIPMENT CABINET, TYPE C	EACH	2	2		
* X0323923	SUPPORT EQUIPMENT AND MAINTENANCE	L SUM	1	1		
* X0323924	SYSTEM IMPLEMENTATION, EQUIPMENT INTEGRATION AND SUPPORT	L SUM	1	1		
X0324092	ITS EQUIPMENT ROOM	L SUM	1	1		
* X0324095	VIDEO WALL DISPLAY	L SUM	1	1		
X0325214	PREFORMED JOINT STRIP SEAL, 4"	FOOT	506			506
X0325305	STRUCTURAL REPAIR OF CONCRETE, DEPTH EQUAL TO OR LESS THAN 5"	SQ FT	3,129			3,129
X0325303	STRUCTURAL REPAIR OF CONCRETE, DEPTH GREATER THAN 5"	SQ FT	1,105			1,105
X8260110	NAVIGATION LIGHTING SYSTEM	L SUM	1		1	
XX003940	20 AMP, 1 POLE CIRCUIT BREAKER	EACH	2	2		
* XX006058	POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	56,224	56,224		
* XX006059	POLYUREA PAVEMENT MARKING - LINE 6"	FOOT	7,028	7,028		
Z0002600	BAR SPLICERS	EACH	168			168
Z0005215	BITUMINOUS STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	60	60		
Z0022400	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	1,235			1,235
△ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0047300	PROTECTIVE SHIELD	SQ YD	31,967			31,967
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1			1
X0325583	REMOVE AND RE-INSTALL FINGER PLATE JOINTS	EACH	28			28
X0325594	LIGHT POLE, ALUMINUM, 45 FT. M.H., 6 FT. DAVIT ARM	EACH	11			
X0325585	LIGHT POLE, ALUMINUM, 45 FT. M.H., 6 FT. DAVIT ARM TWIN	EACH	20		20	
50606000	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES	L SUM	1			1
63200310	GUARDRAIL REMOVAL	FOOT	580	580		
70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	138	138		
70500615	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1	1		
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO.8	FOOT	7,200	7,200		
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	7,200	7,200		

* SPECIALTY ITEM
△ SFTY-3N

COMMITMENTS

1. A commitment has been made to allow no impacts to Wetlands or Threatened and Endangered Species
 2. A commitment has been made to notify the Coast Gaurd if work over the channel goes below 4' from the low beam elevation of the bridge.
- SEE THE RESIDENT ENGINEER FOR THE COMMITMENT FILE ASSOCIATED WITH THIS PROJECT FOR MORE DETAILS

9/1/2006 12:10:01 PM c:\p00\sect\sect0505\der01.s.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE _____ DRAWN BY _____
CHECKED BY _____