

**SUMMARY OF QUANTITIES**

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SUBTOTAL HANCOCK COUNTY	ROADWAY	STRUCTURE	STRUCTURES	ROADWAY	LIGHTING
						SN 034-2007 IL 336 EB & WB OVER TRIBUTARY OF EAST FORK LA MOINE RIVER	SN 034-0511 EB SN 034-0512 WB IL 336 OVER EAST FORK LA MOINE RIVER		
					80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO
					CONSTRUCTION TYPE CODE I000-2A	X028-2A	X081-2A	I000-2A	Y030-1E
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1	1	1				
Z0007604	BUILDING REMOVAL NO. 4	L SUM	1				1		
Z0007606	BUILDING REMOVAL NO. 6	L SUM	1				1		
Z0007607	BUILDING REMOVAL NO. 7	L SUM	1				1		
Z0007608	BUILDING REMOVAL NO. 8	L SUM	1				1		
Z0007609	BUILDING REMOVAL NO. 9	L SUM	1				1		
Z0007610	BUILDING REMOVAL NO. 10	L SUM	1				1		
Z0007611	BUILDING REMOVAL NO. 11	L SUM	1				1		
Z0007612	BUILDING REMOVAL NO. 12	L SUM	1				1		
Z0007613	BUILDING REMOVAL NO. 13	L SUM	1				1		
Z0007614	BUILDING REMOVAL NO. 14	L SUM	1				1		
Z0007615	BUILDING REMOVAL NO. 15	L SUM	1				1		
Z0007616	BUILDING REMOVAL NO. 16	L SUM	1				1		
Z0007617	BUILDING REMOVAL NO. 17	L SUM	1				1		
* Z0008224	DRILLED SHAFT IN SOIL 24"	FOOT	193	193			193		
* Z0008242	DRILLED SHAFT IN SOIL 42"	FOOT	383	383			383		
* Z0008248	DRILLED SHAFT IN SOIL 48"	FOOT	174	174			174		
* Z0008318	DRILLED SHAFT IN ROCK 18"	FOOT	47	47			47		
* Z0008336	DRILLED SHAFT IN ROCK 36"	FOOT	234	234			234		
* Z0008342	DRILLED SHAFT IN ROCK 42"	FOOT	228	228			228		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.25	0.25			0.75	
Z0023900	FILLING EXISTING WELLS	EACH	6	1	1			5	
Z0026305	FURNISHING AND MAINTAINING AUTOMOTIVE VEHICLES	CAL MO	24	6	6			18	
* Z0049801	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1					1	
* Z0049904	REMOVAL AND DISPOSAL OF <sup>NON</sup> FRIABLE ASBESTOS, BUILDING NO. 4	L SUM	1					1	
* Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1					1	
* Z0049909	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 9	L SUM	1					1	
Z0054500	ROCK FILL	TON	186	186	186				
Z0054505	ROCK FILL (REPLACEMENT)	TON	1099	1099		1099			
Z0056100	SAND DRAINAGE BLANKET	CU YD	28910	26710	26710			2200	
Z0065100	SETTLEMENT PLATFORMS	EACH	4	3	3			1	
Z0076600	TRAINEES	HOUR	1500	375	375			1125	
X0325581	MANHOLES, TYPE A, 7' DIAMETER, SPECIAL	EACH	3					3	

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES  
SHEET 8 OF 8**

SCALE: VERT. N/A  
HORIZ. N/A  
DATE 11/7/05

DRAWN BY BDS  
CHECKED BY SRD

Y080 REVISED 11/10/06