

**SUMMARY OF QUANTITIES**

| PAY ITEM NUMBER | PAY ITEM DESCRIPTION   | UNIT  | TOTAL QUANTITY | SUBTOTAL HANCOCK COUNTY | ROADWAY   | STRUCTURE   | STRUCTURES   | ROADWAY   | LIGHTING  |
|-----------------|--|-------|----------------|-------------------------|---|---|--|---|---|
|                 |  |       |                |                         |   | SN 034-2007<br>IL 336 EB & WB<br>OVER TRIBUTARY<br>OF EAST FORK<br>LA MOINE RIVER | SN 034-0511 EB<br>SN 034-0512 WB<br>IL 336 OVER<br>EAST FORK<br>LA MOINE RIVER |   |   |
|                 |  |       |                |                         | 80% FEDERAL<br>20% STATE<br>RURAL<br>HANCOCK CO | 80% FEDERAL<br>20% STATE<br>RURAL<br>HANCOCK CO                                   | 80% FEDERAL<br>20% STATE<br>RURAL<br>HANCOCK CO                                | 80% FEDERAL<br>20% STATE<br>RURAL<br>McDONOUGH CO | 80% FEDERAL<br>20% STATE<br>RURAL<br>McDONOUGH CO |
|                 |  |       |                |                         | 1000-2A   | X028-2A   | X081-2A  | 1000-2A   | Y030-1E   |
| 50101200        | REMOVAL OF EXISTING STRUCTURES NO. 10                                | EACH  | 1              |                         |   |   |  | 1   |   |
| 50102400        | CONCRETE REMOVAL   | CU YD | 48.1           | 48.1                    |   | 48.1  |  |   |   |
| 50105220        | PIPE CULVERT REMOVAL   | FOOT  | 1256           | 129                     | 129   |   |  | 1127  |   |
| 50200100        | STRUCTURE EXCAVATION   | CU YD | 431            | 431                     |   |   | 431  |   |   |
| 50300150        | NEOPRENE EXPANSION JOINT 2"  | FOOT  | 108.5          | 108.5                   |   |   | 108.5  |   |   |
| 50300155        | NEOPRENE EXPANSION JOINT 2 1/2"                                      | FOOT  | 108.5          | 108.5                   |   |   | 108.5  |   |   |
| 50300225        | CONCRETE STRUCTURES  | CU YD | 708.2          | 708.2                   |   |   | 708.2  |   |   |
| 50300255        | CONCRETE SUPERSTRUCTURE  | CU YD | 735.4          | 735.4                   |   |   | 735.4  |   |   |
| 50300260        | BRIDGE DECK GROOVING   | SQ YD | 2201           | 2201                    |   |   | 2201   |   |   |
| 50300265        | SEAL COAT CONCRETE   | CU YD | 1577.3         | 591.5                   | 591.5   |   |  | 985.8   |   |
| 50300300        | PROTECTIVE COAT  | SQ YD | 2201           | 2201                    |   |   | 2201   |   |   |
| 50300310        | ELASTOMERIC BEARING ASSEMBLY, TYPE I                                 | EACH  | 36             | 36                      |   |   | 36   |   |   |
| 50300320        | ELASTOMERIC BEARING ASSEMBLY, TYPE II                                | EACH  | 12             | 12                      |   |   | 12   |   |   |
| 50401105        | FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN. | FOOT  | 2932           | 2932                    |   |   | 2932   |   |   |
| 50500405        | FURNISHING AND ERECTING STRUCTURAL STEEL                             | POUND | 1100           | 1100                    |   |   | 1100   |   |   |
| 50800105        | REINFORCEMENT BARS   | POUND | 177060         | 177060                  | 90  | 66310   | 110660   |   |   |
| 50800205        | REINFORCEMENT BARS, EPOXY COATED                                     | POUND | 279940         | 279940                  |   | 2000  | 277940   |   |   |
| 51500100        | NAME PLATES  | EACH  | 3              | 3                       |   | 1   | 2  |   |   |
| 54001000        | BOX CULVERT END SECTIONS   | EACH  | 2              | 2                       | 2   |   |  |   |   |
| 54002080        | EXPANSION BOLTS 3/4 INCH X 18 INCH                                   | EACH  | 110            | 110                     |   | 110   |  |   |   |
| 54003000        | CONCRETE BOX CULVERTS  | CU YD | 300.7          | 300.7                   |   | 300.7   |  |   |   |
| 54010606        | PRECAST CONCRETE BOX CULVERT 6' X 6'                                 | FOOT  | 283            | 283                     | 283   |   |  |   |   |
| 542A0229        | PIPE CULVERTS, CLASS A, TYPE 1 24"                                   | FOOT  | 109            |                         |   |   |  | 109   |   |
| 542A0235        | PIPE CULVERTS, CLASS A, TYPE 1 30"                                   | FOOT  | 43             |                         |   |   |  | 43  |   |
| 542A0259        | PIPE CULVERTS, CLASS A, TYPE 1 54"                                   | FOOT  | 95             |                         |   |   |  | 95  |   |
| 542A1069        | PIPE CULVERTS, CLASS A, TYPE 2 24"                                   | FOOT  | 938            | 128                     | 128   |   |  | 810   |   |
| 542A1081        | PIPE CULVERTS, CLASS A, TYPE 2 36"                                   | FOOT  | 234            |                         |   |   |  | 234   |   |
| 542A1093        | PIPE CULVERTS, CLASS A, TYPE 2 48"                                   | FOOT  | 349            |                         |   |   |  | 349   |   |
| 542A1909        | PIPE CULVERTS, CLASS A, TYPE 3 24"                                   | FOOT  | 252            | 130                     | 130   |   |  | 122   |   |
| 542A1933        | PIPE CULVERTS, CLASS A, TYPE 3 48"                                   | FOOT  | 98             |                         |   |   |  | 98  |   |
| 542A2761        | PIPE CULVERTS, CLASS A, TYPE 4 36"                                   | FOOT  | 93             |                         |   |   |  | 93  |   |
| 542A2779        | PIPE CULVERTS, CLASS A, TYPE 4 54"                                   | FOOT  | 118            |                         |   |   |  | 118   |   |
| 542D0220        | PIPE CULVERTS, CLASS D, TYPE 1 15"                                   | FOOT  | 170            |                         |   |   |  | 170   |   |
| 542D0223        | PIPE CULVERTS, CLASS D, TYPE 1 18"                                   | FOOT  | 240            |                         |   |   |  | 240   |   |
| 542D0277        | PIPE CULVERTS, CLASS D, TYPE 1 72"                                   | FOOT  | 176            | 176                     | 176   |   |  |   |   |

\* SPECIALTY ITEMS

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
SHEET 3 OF 8

SCALE: VERT. N/A  
HORIZ. N/A  
DATE 11/7/05

DRAWN BY BDS  
CHECKED BY SRD

Plot Date: 8/20/2006  
Plot Time: 12:46:40 PM  
Plotted By: sdcnphue  
Pen Table: ldot.tbl  
Filename: I:\03033\cadd\1\constr\sheet\plmas\004\_summary.dgn