

**SUMMARY OF QUANTITIES**

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SUBTOTAL HANCOCK COUNTY	ROADWAY	STRUCTURE	STRUCTURES	ROADWAY	LIGHTING
						SN 034-2007 IL 336 EB & WB OVER TRIBUTARY OF EAST FORK LA MOINE RIVER	SN 034-0511 EB SN 034-0512 WB IL 336 OVER EAST FORK LA MOINE RIVER		
					80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO
					CONSTRUCTION TYPE CODE				
					1000-2A	X028-2A	X081-2A	I000-2A	Y030-1E
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	122	70	70			52	
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	127					127	
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	234	98	98			136	
542D1075	PIPE CULVERTS, CLASS D, TYPE 2 30"	FOOT	86	86	86				
542D1099	PIPE CULVERTS, CLASS D, TYPE 2 54"	FOOT	77					77	
5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	52					52	
5421A015	PIPE CULVERTS, CLASS A, TYPE 1 15" (TEMPORARY)	FOOT	178	36	36			142	
5421A018	PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY)	FOOT	58					58	
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	118					118	
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	72					72	
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	42					42	
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	36					36	
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	68					68	
54213450	END SECTIONS 15"	EACH	10	2	2			8	
54213453	END SECTIONS 18"	EACH	14					14	
54213459	END SECTIONS 24"	EACH	6	2	2			4	
54213465	END SECTIONS 30"	EACH	2	2	2				
54213489	END SECTIONS 54"	EACH	2					2	
54213507	END SECTIONS 72"	EACH	4	4	4				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	14	2	2			12	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1					1	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2					2	
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	4					4	
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	2					2	
5422A030	PIPE CULVERTS, CLASS A, TYPE 2 30" (TEMPORARY)	FOOT	84					84	
5422D018	PIPE CULVERTS, CLASS D, TYPE 2 18" (TEMPORARY)	FOOT	74					74	
5422D042	PIPE CULVERTS, CLASS D, TYPE 2 42" (TEMPORARY)	FOOT	25					25	
5422D048	PIPE CULVERTS, CLASS D, TYPE 2 48" (TEMPORARY)	FOOT	68					68	
5422D054	PIPE CULVERTS, CLASS D, TYPE 2 54" (TEMPORARY)	FOOT	46					46	
5422D060	PIPE CULVERTS, CLASS D, TYPE 2 60" (TEMPORARY)	FOOT	60	60	60				
54248515	CONCRETE COLLAR	EACH	2	2	2				
58700200	BRIDGE SEAT SEALER	SQ FT	656	656			656		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	166	166			166		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	179	36	36			143	
60107600	PIPE UNDERDRAINS 4"	FOOT	69399	14774	14774			54625	

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
SHEET 4 OF 8

SCALE: VERT. N/A  
HORIZ. N/A  
DATE 11/7/05

DRAWN BY BDS  
CHECKED BY SRD

Plot Date: 8/20/2006  
 Plot Time: 2:46:40 PM  
 Plotted By: sdonohue  
 Pen Table: idot.tbl  
 Filename: R:\03033\cadd\1\construc\ion\_dona\04\_summry.dgn