F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(34-6,55-1)	HANCOCK/ McDONOUGH	433	24
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATE CONTRACT NO. 68206

DRAINAGE STRUCTURES

SIDE	ROAD	STATION	DESCRIPTION	PIPE CULVERTS																																		END SECTIONS										MANHOLES					INLETS			
																																					END SECTIONS						PRECAST RCP																
				6' x 6' PRECAST CONCRETE BOX	TYPE 1, CLASS A, 24 INCH	TYPE 1, CLASS A, 30 INCH	TYPE 1, CLASS A, 54 INCH	TYPE 2, CLASS A, 24 INCH	TYPE 2, CLASS A, 36 INCH	TYPE 2, CLASS A, 48 INCH	TYPE 3, CLASS A, 24 INCH	TYPE 3, CLASS A, 48 INCH	TYPE 4, CLASS A, 36 INCH	TYPE 4, CLASS A, 54 INCH	TYPE 1, CLASS D, 15 INCH	TYPE 1, CLASS D, 18 INCH	TYPE 2, CLASS D, 15 INCH	TYPE 2, CLASS D, 18 INCH	TYPE 2, CLASS D, 24 INCH	TYPE 2, CLASS D, 30 INCH	TYPE 2, CLASS D, 54 INCH	TYPE 1, CLASS A, 12 INCH (TEMPORARY)	TYPE 1, CLASS A, 15 INCH (TEMPORARY)	TYPE 1, CLASS A, 18 INCH (TEMPORARY)	TYPE 1, CLASS A, 24 INCH (TEMPORARY)	TYPE 1, CLASS D, 12 INCH (TEMPORARY)	TYPE 1, CLASS D, 15 INCH (TEMPORARY)	TYPE 1, CLASS D, 18 INCH (TEMPORARY)	TYPE 1, CLASS D, 24 INCH (TEMPORARY)	TYPE 2, CLASS A, 30 INCH (TEMPORARY)	TYPE 2, CLASS D, 18 INCH (TEMPORARY)	TYPE 2, CLASS D, 42 INCH (TEMPORARY)	TYPE 2, CLASS D, 48 INCH (TEMPORARY)	TYPE 2, CLASS D, 54 INCH (TEMPORARY)	TYPE 2, CLASS D, 60 INCH (TEMPORARY)	15 INCH	18 INCH	24 INCH	30 INCH	54 INCH	24 INCH	30 INCH	36 INCH	48 INCH	54 INCH	MH TYPE A, 4 FT. DIA.	MH TYPE A, 5 FT. DIA.	MH TYPE A, 5 FT. DIA. TYPE 1 FRAME, CL LID	MH TY A, SPL, 6 FT. DIA. TY 1 FRAME, CL LID	MH TYPE A, 7 FT. DIA., SPECIAL	TYPE B	MEDIAN INLET (604106), SPECIAL	BOX CULVERT END SECTIONS	CONCRETE COLLAR
				FOOT																																	EACH																
LT	IL 336	1407+19.06	PIPE CULVERT														70																				2																
CL	IL 336	1407+50.00	PIPE CULVERT																			36																															
CL	IL 336	1410+02.84	PIPE CULVERT					38																																									1					1			
LT	IL 336	1415+90.00	PIPE CULVERT																	86																					2														
RT	IL 336	1415+90.00	PIPE CULVERT																98																						2														
LT	IL 336	1416+75.00	PIPE CULVERT					90																																								1					1	1		
LT	IL 336	1434+20.00	PIPE CULVERT								130																																				1				1	1			
RT	IL 336	1440+27.98	PIPE CULVERT																																																			
CL	IL 336	1441+50.00	BOX CULVERT	283																																																2	2
SUBTOTAL HANCOCK COUNTY				283	0	0	0	128	0	0	130	0	0	0	0	0	70	0	98	86	0	0	36	0	0	0	0	0	0	0	0	0	60	2	0	2	2	0	2	0	0	0	0	1	1	1	0	0	1	3	2	2
MCDONOUGH COUNTY																																																						
RT	IL 336	1449+00.00	PIPE CULVERT					90																																								1					1			
RT	IL 336	9+00.00	PIPE CULVERTS																																	44									68								
CL	IL 336	12+27.00	PIPE CULVERT							86		98																																				2				1		1		
RT	IL 336	21+46.21	PIPE CULVERT				95																																										1						
RT	IL 336	22+21.37	PIPE CULVERT			43																																																
RT	IL 336	22+48.00	PIPE CULVERTS								122																																				1	1				1			
RT	IL 336	23+05.00	PIPE CULVERT					104																																								1					1			
LT	IL 336	34+50.00	PIPE CULVERT					92																																								1				1		1		
	IL 336	39+20.00	PIPE CULVERTS																																	42	36																
	IL 336	47+50.00	PIPE CULVERTS																			80	58																															
RT	IL 336	47+57.81	PIPE CULVERT																					50																															
LT	IL 336	50+00.00	PIPE CULVERT					86																																								1					1			
RT	IL 336	56+12.66	PIPE CULVERTS																			26							32																									
CL	IL 336	57+20.00	PIPE CULVERT					177																																								2								
CL	IL 336	72+38.00	PIPE CULVERT						234																																									2			1		1			
LT	IL 336	74+70.00	PIPE CULVERT					84																																								1				1		1		
CL	IL 336	80+85.45	PIPE CULVERT					91					93	118																																		1			1	1		1	2	
LT	IL 336	81+26.18	PIPE CULVERT		34																																										1								
	IL 336	86+88.83	PIPE CULVERT																			26		34						42																							
	IL 336	88+74.59	PIPE CULVERTS																			26		34						42																							
LT	IL 336	91+30.00	PIPE CULVERT					86																																								1					1			
LT	IL 336	102+00.00	PIPE CULVERT																66																						2														
RT	IL 336	102+12.00	PIPE CULVERT																70																						2														
RT	IL 336	102+08.61	PIPE CULVERT																											36																							
CL	IL 336	102+09.14	PIPE CULVERT																			36																															
RT	IL 336	116+60.00	PIPE CULVERT							263																																						2					1		1	
RT	IL 336	129+57.42	PIPE CULVERT																																	28																	
RT	FR 02	193+82.19	PIPE CULVERT														40																						2														
CL	TR 257	301+15.52	PIPE CULVERT																		77																															
RT	IL 61	392+50.00	PIPE CULVERT														46																						2														
LT	IL 61	392+50.00	PIPE CULVERT													46																						2															

CONTINUED ON NEXT SHEET

••• SEE SHEET 29 FOR ADDITIONAL DRAINAGE ITEMS FOR WHITMIRE ACCESS ROAD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
DRAINAGE STRUCTURES

SCALE: VERT. N/A
HORIZ. N/A
DATE 11/9/05

DRAWN BY BDS
CHECKED BY SRD

Plot Date: 8/20/2006
Plot Time: 12:46:43 PM
Plotted By: dsdonahue
Pen Tables: idot.tbl
Filenames: k:\03033\cadd\1\construction_plans\007_schedules.dgn