

GUARDRAIL										
LOCATION STATION TO STATION	SIDE	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 6	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER-DIRECT APPLIED
		FOOT	FOOT	EACH	EACH	FOOT	EACH	EACH	EACH	EACH
HANCOCK COUNTY										
STA 1426+48.13 TO STA 1426+98.13	19' RT EASTBOUND			1					1	1
STA 1427+64.56 TO STA 1428+14.56	21' LT WESTBOUND						1		1	1
STA 1427+94.18 TO STA 1428+44.18	59' RT EASTBOUND			1					1	1
STA 1426+98.13 TO STA 1430+60.62	19' RT EASTBOUND		362.5						4	
STA 1428+14.56 TO STA 1430+27.06	21' LT WESTBOUND					212.5			2	
STA 1428+44.18 TO STA 1430+94.18	59' RT EASTBOUND		250.0						3	
STA 1429+32.00 TO STA 1431+07.00	RT	176								
STA 1429+45.17 TO STA 1429+95.17	59' LT WESTBOUND						1		1	1
STA 1429+95.17 TO STA 1430+26.42	59' LT WESTBOUND							1	1	
STA 1430+27.06 TO STA 1430+58.31	21' LT WESTBOUND							1	1	
STA 1429+98.00 TO STA 1431+38.00	RT	141								
STA 1430+60.62 TO STA 1430+91.87	19' RT EASTBOUND				1					
STA 1430+94.18 TO STA 1431+25.43	59' RT EASTBOUND				1					
STA 1432+79.77 TO STA 1433+11.02	59' LT WESTBOUND				1					
STA 1433+13.34 TO STA 1433+44.59	19' LT WESTBOUND				1					
STA 1433+11.02 TO STA 1435+61.02	59' RT WESTBOUND		250.0						3	
STA 1433+25.00 TO STA 1435+91.00	RT	266								
STA 1433+44.59 TO STA 1437+05.78	19' RT WESTBOUND		363						3	
STA 1433+55.00 TO STA 1435+32.00	RT	178								
STA 1435+61.02 TO STA 1436+09.67	59' LT WESTBOUND			1					1	1
STA 1437+05.78 TO STA 1437+55.33	19' LT WESTBOUND			1					2	1
SUBTOTAL HANCOCK COUNTY		761	1225	4	4	212.5	2	2	24	6
MCDONOUGH COUNTY										
STA 19+13.00 TO STA 20+29.00	RT	127								
SUBTOTAL MCDONOUGH COUNTY		127	0	0	0	0.0	0	0	0	0
PROJECT TOTAL		888	1225	4	4	212.5	2	2	24	6

BRIDGE APPROACH PAVEMENT	
LOCATION STATION TO STATION	BRIDGE APPROACH PAVEMENT SQ YD
IL 336 STA 1430+25.60 TO STA 1430+55.60 (WB STRUCT)	138
IL 336 STA 1430+07.65 TO STA 1430+37.65 (WB STRUCT)	138
IL 336 STA 1430+67.56 TO STA 1430+97.56 (EB STRUCT)	138
IL 336 STA 1433+49.61 TO STA 1433+79.61 (EB STRUCT)	138
SUBTOTAL HANCOCK COUNTY	552
SUBTOTAL MCDONOUGH COUNTY	0
TOTAL PROJECT	552

MODIFIED SOILS				
LOCATION STATION TO STATION	LIME TON	PROCESSING MODIFIED SOILS		
		12" SQ YD	20" SQ YD	24" SQ YD
STA 1400+50.00 TO STA 1431+26.76	522.0	26046		
STA 1432+78.44 TO STA 1442+50.00	160.0	7983		
STA 1448+50.00 TO STA 1451+42.35	52.5	2620		
SUBTOTAL HANCOCK COUNTY	734.5	36649	0	0
STA 0+00.00 TO STA 2+50.00	44.9	2241		
STA 12+50.00 TO STA 22+22.15	191.0	9532		
STA 22+22.15 TO STA 28+00.00	120.7	6025		
STA 28+00.00 TO STA 33+35.00	161.0		4821	
STA 33+35.00 TO STA 42+65.00	167.9	8380		
STA 42+65.00 TO STA 44+30.00	60.1			1498
STA 44+30.00 TO STA 45+30.00	19.4	967		
STA 45+30.00 TO STA 46+30.00	42.1			1051
STA 46+30.00 TO STA 47+30.00	21.9	1094		
STA 47+30.00 TO STA 48+99.10	83.2			2075
STA 48+99.10 TO STA 50+10.00	56.0			1398
STA 50+10.00 TO STA 75+57.07	484.6	24182		
STA 75+57.07 TO STA 95+80.00	379.9	18959		
STA 95+80.00 TO STA 96+35.00	19.8			493
STA 96+35.00 TO STA 115+72.45	364.5	18188		
STA 115+72.45 TO STA 124+35.00	171.4	8551		
STA 124+35.00 TO STA 128+00.00	65.8	3286		
IL 61				
STA 392+98.00 TO STA 399+39.21	83.3			2077
SUBTOTAL MCDONOUGH COUNTY	2537.5	101405	4821	8592
PROJECT TOTAL	3272.0	138054	4821	8592

WHITMIRE ACCESS ROAD					
LOCATION STATION TO STATION	SIDE	PIPE CULVERTS, CLASS D, TYPE 1 72" FOOT	END SECTIONS 72" FOOT	HEAVY DUTY EROSION CONTROL BLANKET	FABRIC FORMED CONCRETE REVETMENT MAT
				SQ YD	SQ YD
STA 1438+99.84	RT	176	2		
STA 1437+93.41 TO STA 1440+14.36	RT				1033.3
STA 1436+00 TO STA 1439+00	RT			1406	
SUBTOTAL HANCOCK COUNTY		176	2	1406	1033.3
PROJECT TOTAL		176	2	1406	1033.3

SAND DRAINAGE BLANKET	
LOCATION STATION	CUBIC YARDS
HANCOCK COUNTY	
STA 1410+00 TO STA 1416+00	6742
STA 1433+29.28 TO STA 1442+00.00	19968
SUBTOTAL HANCOCK COUNTY	26710
STA 15+00 TO 17+00	2200
SUBTOTAL MCDONOUGH COUNTY	2200
PROJECT TOTAL	28910

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
GUARDRAIL, MODIFIED SOILS,
BRIDGE APPROACH PAVEMENT &
SAND DRAINAGE BLANKET

SCALE: VERT. N/A
 HORIZ. N/A
 DATE 11/9/05

DRAWN BY BDS
 CHECKED BY SRD