NOTE: DISTANCES SHALL BE PROVIDED BY IDOT DISTRICT 4 OPERATIONS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(34-6,55-1)	HANCOCK/ McDONOUGH	433	242
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATE CONTRACT NO. 68206

SIGN DETAIL

1:10

SIGN NUMBER	D2-2	
WIDTH x HGHT.	5'-6" x 2'-6"	
BORDER WIDTH	0.75"	
CORNER RADIUS	1.88"	
MOUNTING	Ground	
BACKGROUND	TYPE:	Reflective
	COLOR:	Green
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	White/Pure White

SYMBOL	ROT	X	Y	WID	HT

Panel Style: D2-2.ssi

Dimensions are in inches.tenths

Letter spacings are to start of next letter

LETTER POSITIONS (X)

											LENGTH	SERIES/SIZE
	C	O	L	M	A	R		X				D 2000
6	5.3	5.6	4.6	5.6	6	4.1	18.8	4.1	6		54	6
	A	U	G	U	S	T	A		X			D 2000,EM 2000
6	6	5.4	5.4	5.1	4.6	4.1	5.1	13.1	5.2	6	54	6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SIGN PANEL STANDARDS

SHEET 3 OF 14

SCALE: VERT. N/A HORIZ. N/A

DATE 6/21/04

DRAWN BY BDS

CHECKED BY SRD

Plot Date: 7/19/2006
Plot Time: 10:27:10 AM
Plotted By: bschmidt
Pen Table: idot.tbl
Filename: I:\03033\Cad\T\Construction_Plans\223_DetailsSignPanel.dgn