

| | | | | | |
|-------|-----|------------------------------|--------|-------|-----|
| ROUTE | | SECTION | COUNTY | SHEET | |
| MKD. | FAP | D-4 SHLDR. REPAIR 2007 | KNOX | TOTAL | NO. |
| US 34 | 313 | | | 10 | 7 |

D-94-120-06
CONTRACT NO. 68651

| LOCATION | LENGTH | WIDTH | AREA | BITUMINOUS SURFACE REMOVAL 1 1/2" | BITUMINOUS MATERIALS (PRIME COAT) | BITUMINOUS SHOULDERS SUPERPAVE 2" |
|--------------------|--------|-----------|---------|-----------------------------------|-----------------------------------|-----------------------------------|
| OUTSIDE SHOULDERS | FEET | FEET | SQ. YD. | SQ. YD. | TON | TON |
| EAST BOUND LANES | | | | | | |
| STA. 477+00-481+00 | 400 | 10 ± VAR. | 444.4 | 444.4 | 0.2 | 49.8 |
| STA. 482+67-491+55 | 888 | 10 ± VAR. | 986.7 | 986.7 | 0.4 | 110.5 |
| STA. 491+55-494+35 | 280 | 10 ± VAR. | 311.1 | 311.1 | 0.1 | 34.8 |
| STA. 497+35-499+35 | 200 | 10 ± VAR. | 222.2 | 222.2 | 0.1 | 24.9 |
| STA. 500+30-507+06 | 676 | 10 ± VAR. | 751.1 | 751.1 | 0.3 | 84.1 |
| STA. 507+06-536+95 | 2989 | 10 ± VAR. | 3321.1 | 3321.1 | 1.3 | 372 |
| STA. 539+24-564+52 | 2528 | 10 ± VAR. | 2808.9 | 2808.9 | 1.1 | 314.6 |
| STA. 564+52-607+17 | 4265 | 10 ± VAR. | 4738.9 | 4738.9 | 1.9 | 530.8 |
| WEST BOUND LANES | | | | | | |
| STA. 477+00-484+95 | 795 | 10 ± VAR. | 883.3 | 883.3 | 0.4 | 98.9 |
| STA. 484+95-491+70 | 675 | 10 ± VAR. | 750 | 750 | 0.3 | 84.0 |
| STA. 492+00-494+95 | 295 | 10 ± VAR. | 327.8 | 327.8 | 0.1 | 36.7 |
| STA. 497+35-500+86 | 351 | 10 ± VAR. | 390 | 390 | 0.2 | 43.7 |
| STA. 500+86-509+25 | 839 | 10 ± VAR. | 932.2 | 932.2 | 0.4 | 104.4 |
| STA. 510+85-539+75 | 2890 | 10 ± VAR. | 3211.1 | 3211.1 | 1.3 | 359.6 |
| STA. 539+75-566+68 | 2693 | 10 ± VAR. | 2992.2 | 2992.2 | 1.2 | 335.1 |
| STA. 569+21-607+17 | 3796 | 10 ± VAR. | 4217.8 | 4217.8 | 1.7 | 472.4 |
| TOTAL | | | | 27289 | 11 | 3056 |

RATES:

BITUMINOUS CONCRETE SUPER PAVE=112 LB/SQ YD/IN
BITUMINOUS BITUMINOUS MATERIAL (PRIME COAT)=0.1 GAL/SQ YD

ILLINOIS DEPARTMENT OF TRANSPORTATION

TABULATION OF
BITUMINOUS SHLDR.
QUANTITIES