

PLOT DATE = 8/29/2005  
 FILE NAME = c:\p\projects\0505-103\0505-103.dwg  
 PLOT SCALE = 42.3538 / 1"

CODE NUMBER	ITEMS	UNIT	TOTAL QUANTITY	ROADWAY RESURFACING AND WIDENING X071-2A	X071-2A BRIDGE
20300100	CHANNEL EXCAVATION	CU. YD.	801	801	
20400800	FURNISHED EXCAVATION	CU. YD.	1026	1026	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU. YD.	153		153
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
25000350	SEEDING, CLASS 7	ACRE	0.25	0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	22	22	
25000500	PHOSPORUS FERTILIZER NUTRIENT	POUND	22	22	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	22	22	
25100115	MULCH, METHOD 2	ACRE	0.25	0.25	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25	25	
28000400	PERIMETER EROSION BARRIER	FOOT	720	720	
28100109	STONE RIPRAP, CLASS A5	SO. YD.	1,002		1,002
28101300	DUMPED RIPRAP, SPECIAL	TON	345		345
28200200	FILTER FABRIC	SO. YD.	1,002		1,002
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	91	91	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO. YD.	109	109	
42001300	PROTECTIVE COAT	SO. YD.	240	240	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO. YD.	240	240	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO. YD.	48	48	
44000100	PAVEMENT REMOVAL	SO. YD.	370	370	
44000700	APPROACH SLAB REMOVAL	SO. YD.	152	152	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	118	118	
48202900	BITUMINOUS SHOULDERS SUPERPAVE (VARIABLE DEPTH)	SO. YD.	170	170	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU. YD.	243		243
50300100	FLOOR DRAINS	EACH	20		20
50300225	CONCRETE STRUCTURES	CU. YD.	164.3		164.3
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	286		286
50300260	BRIDGE DECK GROOVING	SO. YD.	812		812
50300300	PROTECTIVE COAT	SO. YD.	1,040		1,040
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L. SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	3,384		3,384
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	73,780		73,780
51201400	FURNISHED STEEL PILES HP10x42	FOOT	1,589		1,589
51202700	DRIVING STEEL PILES	FOOT	1,589		1,589

CONTRACT NO. 70344

F.A.P. RTE. 326	SECTION 129BR-31BR	COUNTY CHAMPAIGN	TOTAL SHEETS 30	SHEET NO. 3
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

80% FED  
20% ST

CODE NUMBER	ITEMS	UNIT	TOTAL QUANTITY	ROADWAY RESURFACING AND WIDENING X071-2A	X071-2A BRIDGE
51203400	TEST PILE STEEL HP10x42	EACH	4		4
51500100	NAME PLATES	EACH	1		1
59100100	GEOCOMPOSITE WALL DRAIN	SO. YD.	75		75
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	141		141
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	537.5	537.5	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	798	798	
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L. SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	136	136	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	1762	1762	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO. FT.	46	46	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1762	1762	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3	
78200405	GUARDRAIL MARKERS	EACH	9	9	
78200500	BARRIER WALL MARKERS	EACH	5	5	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4	
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SO. YD.	1,020		1,020
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE. MIX "C", N70	TON	62	62	
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE. IL-19.0, N70	TON	92	92	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 2	EACH	1		1
Z0002600	BAR SPLICERS	EACH	76		76
Z0037300	PAVEMENT GROOVING	SO. YD.	240	240	
Z0038700	PERMANENT BENCHMARKS	EACH	1		1

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.  
DATE:           HORIZ.

DRAWN BY  
CHECKED BY TMW