CONTRACT NO. 70387

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
717	(111B)BR	DEWITT	53	13
STA. 1066+00.00	TO STA. 1172+00.00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

BENCHMARK TBM #53:
CHISELED SQUARE ON TOP OF NORTHEAST WINGWALL OF STRUCTURE.
STA. 1070+08; 17.5' LT.; ELEV. = 692.15

PERMANENT BENCH MARKS, 1 EACH AT SAME LOCATION

SEC. 28, T. 20 N., R. 2 E., 3rd P.M.

N

1"=20'
0' 5' 10' 15' 20' 40' 60'

BRIDGE APPROACH PAVEMENT
FLEXIBLE CONNECTOR
PROPOSED S.N. 020-0063
STEEL BEAM 36" WF
STATION 1069+54.00
TWO SPANS
SKEW = 30°

EXISTING S.N. 020-0007
PRECAST PRESTRESSED CONCRETE DECK BEAMS
STATION 1069+98.00
TWO SPANS
SKEW = 0°

EXISTING R.O.W. LINE
TEN MILE CREEK
61'
BRIDGE APPROACH PAVEMENT
FLEXIBLE CONNECTOR

MATCHLINE STATION 1066+00.00
MATCHLINE STATION 1072+00.00
EXISTING R.O.W. LINE
40'
13'
3'
39'
1066 1067 1068 1069 1070+00 1071
℄ F.A.P. 717 (IL ROUTE 10)
BEGIN PROJECT
END PROJECT
20+00

1068+52.59
1068+34.11
1070+73.89
1070+55.41

+18.00 +38.00 +44.00 +74.00 BK. OF ABUT.
+34.00 BK. OF ABUT. +64.00 +70.00 +90.00

1068+50.00
40.00' RT.
1068+50.00
105.00' RT.
TEMPORARY EASEMENT
EXISTING R.O.W. LINE
FLOW
12'

1070+07.48
50.00' RT.
TEMPORARY EASEMENT
1071+00.00
50.00' RT.
1071+14.07
51.40' RT.

Parcel 5306001
Patricia Ann LeComte

Parcel 5306001
Patricia Ann LeComte

Parcel 5306002
George J. & Patricia Ann LeComte

SEC. 33, T. 20 N., R. 2 E., 3rd P.M.

EXISTING ℄ PROFILE
PROPOSED ℄ PROFILE

+18.00 694.49 -0.15% MATCH +44.00 694.45 +0.11% +64.00 694.69 +0.46% MATCH +90.00 694.81

689.70
686.87
689.89
D.H.W.E. 688.2
687.06

695 690 685 680 675 670 665 660 655

PROPOSED LOW BEAM ELEVATIONS: 690.33 690.35 690.38 690.41 690.44 690.46
PROPOSED BRIDGE OPENING ELEVATONS: 677.05 676.75 676.75 682.74 682.96 685.39
EXISTING LOW CHORD ELEVATIONS: 692.09 692.09 692.10 692.11
EXISTING BRIDGE OPENING ELEVATIONS: 678.62 681.28 682.18 683.98

CENTERLINE ELEVATIONS:
695.29 695.16 695.02 694.89 694.76 694.70 694.63 694.57 694.51 694.47 694.48 694.44 694.46 694.40 694.48 694.37 694.51 694.37 694.54 694.36 694.57 694.39 694.59 694.42 694.62 694.52 694.65 694.64 694.68 694.75 694.74 694.86 695.10 695.34 695.58 695.82

1066+00 1066+50 1067+00 1067+50 1068+00 1068+50 1069+00 1069+50 1070+00 1070+50 1071+00 1071+50 1072+00

TRAFFIC BARRIER TERMINAL TYPE 6

STATION	OFFSET	TO STATION	OFFSET	EACH
1068+34.11	RT.	1068+64.76	RT.	1
1068+52.59	LT.	1068+83.24	LT.	1
1070+24.76	RT.	1070+55.41	RT.	1
1070+43.24	LT.	1070+73.89	LT.	1
		TOTAL		4

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / GRADES CHECKED / BEAM, NOTES & PAVEMENT NOTATIONS CHK'D / NOTE BOOK / NO. / BY / DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / BEAM, NOTES & PAVEMENT NOTATIONS CHK'D / NOTE BOOK / NO. / BY / DATE

PLOT DATE = 8/24/2006
FILE NAME = c:\projects\s503004 (v8\20pp.dgn
PLOT SCALE = 42.3521 ' / IN.
USER NAME = pierson