

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	(122BR)BR	COLES	49	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY HBBRP TWO-LANE RURAL ROADWAY 80% FEDERAL 20% STATE X081-2A
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	498
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	229
2020010	EARTH EXCAVATION	CU YD	125
2030010	CHANNEL EXCAVATION	CU YD	1429
2040080	FURNISHED EXCAVATION	CU YD	12
2070040	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	163
2500020	SEEDING, CLASS 2	ACRE	1
2500035	SEEDING, CLASS 7	ACRE	1
2500040	NITROGEN FERTILIZER NUTRIENT	POUND	90
2500050	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90
2500060	POTASSIUM FERTILIZER NUTRIENT	POUND	90
2510015	MULCH, METHOD 2	ACRE	1
2800025	TEMPORARY EROSION CONTROL SEEDING	POUND	100
2800030	TEMPORARY DITCH CHECKS	EACH	2
2800040	PERIMETER EROSION BARRIER	FOOT	422
2810010	STONE RIPRAP, CLASS A4	SO YD	1911
2820020	FILTER FABRIC	SO YD	1911
4060010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	132
4060030	AGGREGATE (PRIME COAT)	TON	4
4060098	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO YD	192
4060099	TEMPORARY RAMP	SO YD	135
4200165	BRIDGE APPROACH PAVEMENT	SO YD	222
4200130	PROTECTIVE COAT	SO YD	228
4200430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	44
4400010	PAVEMENT REMOVAL	SO YD	222
4400070	APPROACH SLAB REMOVAL	SO YD	126
4400430	BITUMINOUS SHOULDER REMOVAL	SO YD	64
4810200	AGGREGATE SHOULDERS, TYPE B	TON	84
5010010	REMOVAL OF EXISTING STRUCTURES	EACH	1
5010520	REMOVE EXISTING CULVERTS	FOOT	136
5020010	STRUCTURE EXCAVATION	CU YD	374
5030010	FLOOR DRAINS	EACH	30
50300225	CONCRETE STRUCTURES	CU YD	135.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	316.0
50300260	BRIDGE DECK GROOVING	SO YD	823

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY HBBRP TWO-LANE RURAL ROADWAY 80% FEDERAL 20% STATE X081-2A
50300300	PROTECTIVE COAT	SO YD	1086
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	1708
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7810
51201400	FURNISHING STEEL PILES HPI0X42	FOOT	462
51201600	FURNISHING STEEL PILES HPI2X53	FOOT	891
51202700	DRIVING STEEL PILES	FOOT	1353
51500100	NAME PLATES	EACH	1
54213447	END SECTIONS 12"	EACH	2
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	87
60100945	PIPE DRAINS 12"	FOOT	62
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	152
60600305	CONCRETE CURB (DOWELLED)	FOOT	12
60900130	TYPE B INLET BOX, STANDARD 609001(SPECIAL)	EACH	2
60900515	CONCRETE THRUST BLOCKS	EACH	2
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	237.5
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
63100167	TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT)	EACH	2
63100169	TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (FLARED)	EACH	2
63200310	GUARDRAIL REMOVAL	FOOT	605
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1441
70300200	TEMPORARY PAVEMENT MARKING	FOOT	1514
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	985
70400100	TEMPORARY CONCRETE BARRIER	FOOT	525

\* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
**SHEET 1 OF 2**  
 DATE 1/06  
 DRAWN BY MLO  
 CHECKED BY PBB

PLOT DATE = 8/14/2006  
 FILE NAME = c:\pwworkspace\749133\1\749133.dwg  
 PLOT SCALE = 42.933' / IN.  
 USER NAME = erange