

teoslejck  
9/1/2006  
c:\projects\74148d\sched\_schedule

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
770	(115,116)BR	SHELBY & MOULTRIE	77	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 74148	

**EXPLORATION TRENCH SCHEDULE**

LOCATION	EXPLOR TRENCH 52 (FOOT)
RT STA 635+70.00 TO 643+50.00	780
LT STA 638+86.00 TO 640+86.00	200
LT STA 770+38.00 TO 776+07.00	569
RT STA 771+48.00 TO 773+48.00	200
LT STA 831+27.00 TO 835+00.00	373
RT STA 832+59.00 TO 834+59.00	200
<b>TOTALS</b>	<b>2322</b>
USE	2322

**PERMANENT BENCHMARKS, TYPE 1**

LOCATION	EACH
STA. 639+86	1
STA. 772+48	1
STA. 833+59	1
<b>TOTAL</b>	<b>3</b>
USE	3

**RIGHT-OF-WAY MARKER SCHEDULE**

LOCATION	FUR ERECT ROW MARKERS (EACH)
40.00' RT STA 638+05.00	1
70.00' RT STA 638+05.00	1
40.00' LT STA 638+50.00	1
75.00' LT STA 638+50.00	1
75.00' LT STA 640+00.00	1
50.00' LT STA 641+00.00	1
70.00' RT STA 641+10.00	1
40.00' RT STA 641+10.00	1
50.00' LT STA 643+25.00	1
40.00' LT STA 643+25.00	1
40.00' LT STA 770+85.00	1
70.00' LT STA 770+85.00	1
40.00' RT STA 770+90.00	1
75.00' RT STA 770+90.00	1
75.00' RT STA 773+90.00	1
40.00' RT STA 773+90.00	1
70.00' LT STA 774+05.00	1
40.00' LT STA 774+05.00	1
40.00' RT STA 830+00.00	1
45.00' RT STA 830+00.00	1
40.00' LT STA 831+20.00	1
65.00' LT STA 831+20.00	1
45.00' RT STA 831+85.00	1
65.00' RT STA 831+85.00	1
65.00' LT STA 835+50.00	1
45.00' LT STA 835+50.00	1
65.00' RT STA 836+15.00	1
40.00' RT STA 836+15.00	1
40.00' LT STA 837+25.00	1
45.00' LT STA 837+25.00	1
40.00' RT STA 840+90.00	1
50.00' RT STA 840+90.00	1
50.00' RT STA 841+90.00	1
40.00' RT STA 841+90.00	1
<b>TOTAL</b>	<b>34</b>

**BOX CULVERT SCHEDULE**

LOCATION	PCBC 10X10 (M273) (FT)	BOX CUL END SEC			POROUS GRAN BACKFILL (CU YD)
		NO. 1 (EACH)	NO. 2 (EACH)	NO. 3 (EACH)	
639+86.00	144	2			234.3
772+48.00	150		2		277.2
833+59.00	98			2	241.1
<b>TOTALS</b>	<b>392</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>752.6</b>

**NAME PLATE SCHEDULE**

LOCATION	EACH
STA. 639+86	1
STA. 772+48	1
STA. 833+59	1
<b>TOTAL</b>	<b>3</b>
USE	3

**TREE REMOVAL SCHEDULE**

LOCATION	TREE REMOV 6-15 (UNIT)	TREE REMOV OVER 15 (UNIT)	TREE REMOV ACRES (ACRE)
40' LT 640+87.2		38	
41' LT 641+32.3	10		
37' LT 770+81		39	
LT 771+15 772+30			0.025
45' LT 771+15		26	
RT 771+17 772+18			0.015
RT 772+40 773+09			0.047
46' LT 991+40		46	
45' LT 771+65		18	
RT 830+00 833+47			0.117
RT 833+58 834+67			0.055
RT 835+28 836+15			0.015
<b>TOTAL</b>	<b>10</b>	<b>167</b>	<b>0.274</b>
USE	10	167	0.28

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 770 (ILLINOIS ROUTE 128)

**SCHEDULE OF QUANTITIES**

SCALE: N/A  
DATE: 03-20-06

DRAWN BY: MLS  
CHECKED BY: MBF