F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
770	(116,115)RS-2 &114RS-3	SHELBY & MOULTRIE	77	32
STA. 630+00.00	TO STA. 688+00.00			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SHEET 15 OF 17

0 100' 200'
SCALE IN FEET

SE. 1/4 SEC. 12, T 13. N., R 3 E., 3rd P.M.

SW. COR., SEC. 12-13-3
SPIKE NAIL FOUND

S 89° 35' 15" W 5240.26'
SOUTH LINE SEC. 12-13-3

NW. COR., NE.1/4
SEC. 12-13-3
IRON PIN FOUND
EAST SIDE OF STONE
PER MONUMENT RECORD
BOOK 2 PAGE 5

NORTH LINE SEC. 12-13-3
S 89° 47' 01" W 2622.22'

5622051
LARRY OWENS AND BARBARA OWENS
JOINT TENANTS

TOTAL R.O.W. AREA REQUIRED = 0.688 AC.±
AREA IN EXISTING R.O.W. = 0.464 AC.±
NET R.O.W. AREA REQUIRED = 0.224 AC.±
TOTAL AREA REMAINING = 39.312 AC.±
(REMAINING AREAS ARE ESTIMATES)

JOHN AND FERN KEILMAN

2500N (TR 10)
(40')
632+97.38
40.00' LT.
EAST LINE NE 1/4
SEC. 13-13-3
N 00° 23' 47" W
31.68'
SE. COR., SEC. 12-13-3
MONUMENT VAULT FOUND PER
MONUMENT RECORD 1 PAGE 442
632+97.37 4.49' RT.
P.I. STA. EQ. 633+22.98 (BK)=
(NO CURVE) 633+18.57 (AH)
638+50.00
75.00' LT.
638+50.00
3.15' RT.
CONSTRUCTION LIMITS
5622051
PROPOSED
R.O.W. LINE
640+00.00
75.00' LT.
641+00.00
50.00' LT.
643+25.00
50.00' LT.
643+25.00
2.02' RT.
646+17.91
40.00' LT.
℄ FAP 770 (IL 128)
N 00° 27' 23" W
P.I. STA. EQ. 650+40.37 (BK)=
(NO CURVE) 650+44.78 (AH)
℄ FAP 770 (IL 128)
N 00° 31' 10" W
NW. COR., FRACT.
SEC. 7-13-4
PK NAIL SET
686+21.57. 4.17' LT.
630
635
640
645
650
655
EXISTING R.O.W. LINE
EXISTING R.O.W. LINE
CONSTRUCTION LIMITS
638+05.00
3.26' RT.
PROPOSED R.O.W. LINE
638+05.00
70.00' RT.
641+10.00
70.00' RT.
641+10.00
2.53' RT.
EAST LINE SEC. 12-13-3
N 00° 35' 35" W 5300.53'
646+70.71
40.00' RT.
(210.94')
(206.50')
648+77.13
40.00' RT.
NE. COR., SEC. 12-13-3
MONUMENT VAULT FOUND
685+97.89. 4.17' LT.
EAST LINE SE. 1/4
SEC. 1-13-3
N 00° 34' 02" W
23.68'
SW. COR., FRACT.
SEC. 7-13-4
PK NAIL SET
632+65.69 4.47' RT.
632+67.52
40.00' RT.
LAND ACQUISITION
PROJECT OMISSION
ENDS STATION 638+05.00
5622050
641+10.00
2.53' RT.
LAND ACQUISITION PROJECT
OMISSION BEGINS
STATION 643+25.00
N 89° 38' 55" E 4653.24'
SOUTH LINE FRAC. SEC. 7-13-4
NORTH LINE FRAC. SEC. 7-13-4
N 89° 05' 40" W 1664.47'

5622050
WILLIAM M. BAIRD, CAROLYN J. STUPIN, BARBARA A. HOLOWKA,
MARGARET E. MCCLINTOCK, AND JAMES W. BAIRD
AS TRUSTEES UNDER A DECLARATION OF TRUST DATED JUNE 7, 2001

TOTAL R.O.W. AREA REQUIRED = 0.470 AC.±
AREA IN EXISTING R.O.W. = 0.260 AC.±
NET R.O.W. AREA REQUIRED = 0.210 AC.±
TOTAL AREA REMAINING = 66.82 AC.±
(REMAINING AREAS ARE ESTIMATES)

S. PAULINE LUMSDEN

SW. 1/4 FRACTIONAL SEC. 7, T 13. N., R 4 E., 3rd P.M.

SE. COR., FRAC.
SEC. 7-13-4
IRON PIN FOUND

NE. COR., NW. 1/4,
FRACT. SEC. 7-13-4
IRON PIN FOUND

SEE SHEET 14 OF 17
SEE SHEET 16 OF 17

SECTIONS IN THIS PROJECT THAT HAVE RIGHT-OF-WAY TAKING
SEC. 1, T 11 N., R 3 E., 3RD P.M.
SECS. 1, 12, 13, 24, 25, 36, T 12 N., R 3 E., 3RD P.M.
SECS. 12, 36, T 13 N., R 3 E., 3RD P.M.
SECS. 25, 36, T 14 N., R 3 E., 3RD P.M.
SEC. 6, T 11 N., R 4 E., 3RD P.M.
SECS. 6, 7, 18, 19, 30, 31, T 12 N., R 4 E., 3RD P.M.
SECS. 7, 31, T 13 N., R 4 E., 3RD P.M.
SECS. 30, 31, T 14 N., R 4 E., 3RD P.M.

NOTES:
BEARINGS BASED ON ILLINOIS STATE PLANE COORDINATES, EAST ZONE NAD 83 (1997).
⊠ R.O.W. MARKER FOUND
● IRON PIN OR PIPE FOUND
×—×— EXISTING FENCE
○ FENCE POST FOUND
( ) RECORD DATA

PARCELS 52 & 53 WERE DELETED FROM THIS PROJECT

TOWNSHIP ROAD CENTERLINES ARE SURVEY/CONSTRUCTION CENTERLINES AND ARE NOT CENTERLINE OF EXISTING RIGHT OF WAY.

DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 770 (ILLINOIS ROUTE 128)
RIGHT OF WAY PLANS

SECTION (116,115)RS-2&114RS-3
COUNTY SHELBY / MOULTRIE
JOB NO. R-95-062-02
STA. 630+00.00 TO STA. 688+00.00
DRAWN SB CHECKED BY MC/GF
SCALE 1"=100' SHEET 15 OF 17