

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
805	122-VBR-1	ST. CLAIR	58	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FEDERAL 20% STATE X071-2A	80% FEDERAL 20% STATE SFTY-3N
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	214	214	
28100105	STONE RIPRAP, CLASS A3	SQ YD	294	294	
28200200	FILTER FABRIC	SQ YD	294	294	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	972	972	
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	972	972	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.7	0.7	
40800030	AGGREGATE (PRIME COAT)	TON	3.1	3.1	
42001300	PROTECTIVE COAT	SQ YD	1867	1867	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	570	570	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	114	114	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	952	952	
42400610	TEMPORARY SIDEWALK	SQ FT	3448	3448	
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	1032	1032	
44000100	PAVEMENT REMOVAL	SQ YD	876	876	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2344	2344	
44000600	SIDEWALK REMOVAL	SQ FT	1354	1354	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	6402	6402	
44003100	MEDIAN REMOVAL	SQ FT	2347	2347	
50102400	CONCRETE REMOVAL	CU YD	20.3	20.3	
50104650	SLOPE WALL REMOVAL	SQ YD	22	22	
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1	1	
50300100	FLOOR DRAINS	EACH	42	42	
50300225	CONCRETE STRUCTURES	CU YD	12.3	12.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	528.1	528.1	
50300260	BRIDGE DECK GROOVING	SQ YD	1248	1248	
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24	24	
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12	12	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6730	6730	
50500505	STUD SHEAR CONNECTORS	EACH	3024	3024	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	124660	124660	
51500100	NAME PLATES	EACH	1	1	
54215547	METAL END SECTIONS 12"	EACH	2	2	
58700200	BRIDGE SEAT SEALER	SQ FT	639	639	
59000100	EPOXY CRACK SEALING	FOOT	118.5	118.5	
60100945	PIPE DRAINS 12"	FOOT	156	156	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FEDERAL 20% STATE X071-2A	80% FEDERAL 20% STATE SFTY-3N
60500060	REMOVING INLETS	EACH	4	4	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1645	1645	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	699	699	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	4763	4763	
60619700	CONCRETE MEDIAN, TYPE SB-6.12 (DOWELLED)	SQ FT	2596	2596	
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	4	4	
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	537.5	537.5	
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	664	664	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18	
67100100	MOBILIZATION	L SUM	1	1	
70101200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431 (SPECIAL)	EACH	2	2	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701521 (SPECIAL)	EACH	2	2	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	102	102	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	907	907	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	104.4	104.4	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13875	13875	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1642	1642	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	712.5	712.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	662.5	662.5	
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	34.8	34.8	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3820	3820	
*78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	1155	1155	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	17	17	
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6	

10/19/2006
 c:\p\projects\ad01760\plan\sh-097.dgn
 PREP

*SPECIALTY ITEMS

PLOT DATE: 10/19/2006