

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		BRIDGE X080-2A SN 079-0016	SFTY-3N
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1998	1998	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	510	510	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	510	510	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	667	667	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	4	4	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	539	539	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2	
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	151	151	
X0324952	DETOUR SIGNING	L SUM	1	1	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	302	302	
X0656180	PARTIAL DEPTH PATCHING (SPECIAL)	SQ YD	733	733	
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	106	106	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	4	4	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	10	10	
X7200200	WIDE LOAD SIGNING	L SUM	1	1	
X8002137	EROSION AND SEDIMENT CONTROL	SUM	1	1	
XX005495	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH), SPECIAL	SQ FT	151	151	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2
X0325599	PARTIAL DEPTH PATCHING 2"	TON	82	82	
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	733	733	



PLOT DATE = 8/24/2005
 FILE NAME = c:\pwworkspace\10303885\plott\p10303885.dgn
 PLOT SCALE = 43.9333' / IN.
 REFERENCE = *REF*

* SPECIALTY ITEMS

Rev.