

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
329	126BR-1	RANDOLPH	27	3
STA.		TO STA.		
CONTRACT NO. 76898				

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		BRIDGE X080-2A SN 079-0016	SFTY-3N
20200100	EARTH EXCAVATION	CU YD	46	46	
20400800	FURNISHED EXCAVATION	CU YD	1550	1550	
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5	
25100105	MULCH, METHOD 1	ACRE	0.5	0.5	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250	250	
28100109	STONE RIPRAP, CLASS A5	SQ YD	925	925	
28200200	FILTER FABRIC	SQ YD	925	925	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.1	0.1	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	231	231	
44200065	PAVEMENT PATCHING, TYPE II, 6 INCH	SQ YD	15	15	
44200069	PAVEMENT PATCHING, TYPE III, 6 INCH	SQ YD	29	29	
44200071	PAVEMENT PATCHING, TYPE IV, 6 INCH	SQ YD	37	37	
48202700	BITUMINOUS SHOULDERS SUPERPAVE 9"	SQ YD	53	53	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	0.7	0.7	
50300225	CONCRETE STRUCTURES	CU YD	0.7	0.7	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	0.1	0.1	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	4983	4983	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	334	334	
51500100	NAME PLATES	EACH	1	1	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	562	562	
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	1510	1510	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	617	617	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	500	500	
63303290	REMOVE AND SALVAGE EXISTING TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10	
67100100	MOBILIZATION	L SUM	1	1	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70102015	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1020	1020	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1020	1020	

* SPECIALTY ITEMS

Rev.