

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	I-1BR-1	ST. CLAIR	29	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	X080-2A	SFTY-3N	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2		
40600300	AGGREGATE (PRIME COAT)	TON	1	1		
40600990	TEMPORARY RAMP	SQ YD	179	179		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1290	1290		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	547	547		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	214.5	214.5		
44000600	SIDEWALK REMOVAL	SQ FT	1290	1290		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1		
50102400	CONCRETE REMOVAL	CU YD	7.3	7.3		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	62.3	62.3		
50300260	BRIDGE DECK GROOVING	SQ YD	607	607		
50300300	PROTECTIVE COAT	SQ YD	840	840		
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	767	767		
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	6891	6891		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	17550	17550		
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	248	248		
51401600	TEMPORARY BRIDGE RAIL	FOOT	220	220		
51500100	NAME PLATES	EACH	1	1		
60260100	INLETS TO BE ADJUSTED	EACH	2	2		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	214.5	214.5		
X63100110	TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	42	42		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	14	14		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70102672	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602, SPECIAL	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	60	60		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3615	3615		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	975	975		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	356	356		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1570	1570		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	X080-2A	SFTY-3N	
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	550	550		
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	337.5	337.5		
X78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1042	1042		
X78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	229	229		
X78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	545	545		
X78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	127	127		
X78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10		
X78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	11	11		
X78100300	REPLACEMENT REFLECTOR	EACH	16	16		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	574	574		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	37	37		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	276	276		
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	46	46		
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	33	33		
X7200200	WIDE LOAD SIGNING	L SUM	1	1		
Z0002600	BAR SPLICERS	EACH	234	234		
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2		2	
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1		1	
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	1		1	
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2		2	

PLOT DATE = 8/22/2006
 PLOT NAME = c:\p06\p06a\100305\plan\100305.dgn
 PLOT SCALE = 1/4" = 1'-0"
 REFERENCE = #REF#

Rev.