

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
02-00090-00-BT	DUPAGE	117	3
STA. TO STA.			
IDOT PROJECT NO. M-8003(222)			
SALT CREEK GREENWAY TRAIL			
CONTRACT NO. 83713			

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY	DUPAGE FOREST PRESERVE (1)		VILLAGE OF ADDISON (2)		ADDISON PARK DISTRICT (3)	
				BIKEWAY	STRUCTURES	BIKEWAY	STRUCTURES	BIKEWAY	STRUCTURES
				Y047	X032-2A	Y047	Y007	Y047	X032-2A
M2010110	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER)	UNIT	5,291	3978		52		1261	
M2010210	TREE REMOVAL ( OVER 15 UNITS DIAMETER)	UNIT	2,682	2200		18		464	
20101200	TREE ROOT PRUNING	EACH	10	10					
M2020010	EARTH EXCAVATION	CU M	3,927	3279		89		559	
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	13,219	9370		1043		2806	
M2040800	FURNISHED EXCAVATION	CU M	6,710	3640		994		2076	
M2070420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU M	715	506		82		127	
M2080150	TRENCH BACKFILL	CU M	48	33		3		12	
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	21,472	15,339		2417		3716	
M2113150	TOPSOIL FURNISH AND PLACE, 150 MM	SQ M	29,285	21,386		1679		6220	
M2130102	EXPLORATION TRENCH 1.2 METER DEPTH	METER	6	6					
M2500115	SEEDING, CLASS 1B	HA	0.8	0.6				0.2	
M2500312	SEEDING, CLASS 4A	HA	3.1	2.2				0.9	
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	410	280		20		110	
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	410	280		20		110	
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	410	280		20		110	
M2510105	MULCH, METHOD 1	HA	3.9	2.8				1.1	
M2510630	EROSION CONTROL BLANKET	SQ M	2,000	1500				500	
M2520110	SODDING, SALT TOLERANT	SQ M	2,823			2823			
M2520200	SUPPLEMENTAL WATERING	UNIT	5			5			
28000300	TEMPORARY DITCH CHECKS	EACH	42	25				17	
M2800400	PERIMETER EROSION BARRIER	METER	9,483	6109				3374	
M2810103	STONE RIPRAP, CLASS A2	SQ M	9					9	
M2820200	FILTER FABRIC	SQ M	9					9	
M3511100	AGGREGATE BASE COURSE, TYPE B 100MM	SQ M	559	384		175			
M3511150	AGGREGATE BASE COURSE, TYPE B 150 MM	SQ M	17,010	11,926		1950		3134	
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	14,540	9456		1950		3134	
M4205200	PROTECTIVE COAT	SQ M	3,156	914		2242			
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	100			100			
M4240150	PORTLAND CEMENT CONCRETE SIDEWALK 150MM	SQ M	595	420		175			
M4402000	PAVEMENT REMOVAL	SQ M	1,343	1343					
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	47			47			
M4402030	GUTTER REMOVAL	METER	83			83			
M4402045	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	METER	49	22		27			
M4402050	SIDEWALK REMOVAL	SQ M	75	75					
M5010465	SLOPE WALL REMOVAL	SQ M	480		135		345		
M5010522	PIPE CULVERT REMOVAL	METER	10	10					

REVISIONS		
NO.	NAME	DATE

**URS** 1701 GOLF ROAD, SUITE 1000 TEL (847) 228-0707  
ROLLING MEADOWS, IL 60008 FAX (847) 228-1115

VILLAGE OF ADDISON  
**SALT CREEK GREENWAY TRAIL**

SUMMARY OF QUANTITIES

DATE: 5/10/06 DRAWN BY: MIA&VP  
DESIGNED BY: MIA CHECKED BY: DDL