

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	04-00040-00-LS	COOK	31	3
F.H.W.A. REG.	ILLINOIS	PROJECT:	F-0358(028)	
CONTRACT NUMBER 83863				

### SUMMARY OF QUANTITIES

4003

20201200	Removal and Disposal of Unsuitable Material	CY	569
20200100	Earth Excavation	CY	200
<del>XX006699</del>	<del>Sub-Base Granular Material Ty B, 4"</del>	<del>TON</del>	<del>214</del>
20700110	Porous Granular Embankment	TON	407
21101685	Topsoil Furnish and Place, 24"	SY	1,026
* A2004716	Trees, Gleditsia Triacanthos Inermis Shademaster 2"	EA	32
* C2002224	Shrubs, Cotoneaster Hessei, 2' width balled and burlapped	EA	12
28000510	Inlet Filters	EA	28
60618100	Bituminous Concrete Median	SQ FT	5,184
44000500	Combination Curb and Gutter Removal	FT	2,484
44001400	Bituminous Median Surface Removal	SY	1,706
44002010	Concrete Median Removal	FT	212
60107600	Pipe Underdrains, 4"	FT	498
60265305	Median Inlet (604101) to be adjusted	EA	3
60605100	Combination Curb and Gutter, B6.24 Abutting Existing Pavement	FT	1,098
60608523	Combination Curb and Gutter, M2.24 (Dowelled)	FT	1,386
60601805	Concrete Curb Transition	FT	160
67100100	Mobilization	LS	1
70101700	Traffic Control and Protection	LS	1
* 78005110	Epoxy Pavement Marking, 4"	LF	2,484
* D2C00918	Evergreen Juniperus Horizontalis Hughes (creeping juniper) 18" width	EA	215
* K0030415	Perennial Plants, Mixed Daylilies 1/2 gallon pots	UNIT	300
* K1003439	Landscape Fabric	SQ YD	885
XX005840	Flagstone Sidewalk Special	SQ FT	1,600
* XX005856	Mulch- Shredded Hardwood Bark, 3" depth	CU YD	80
* X0322859	Weed Control, Pre-emergent Granular Herbicide	LBS	2

\*SPECIALTY ITEMS

NO.	ITEM	AC TYPE	VOIDS	MAX RAP %
1	BITUMINOUS CONCRETE MEDIAN SUPERPAVE, MIX "C", N50	PG 64-22	4% @ 50 GYR	15%

NOTE:

"THE UNIT WEIGHT USED TO CALCULATE ALL BITUMINOUS SURFACE MIXTURES IS 112 LBS/SQ. YD./IN."

**MORRIS ENGINEERING, INC.**

5100 S. LINCOLN SUITE 100 • LISLE, ILLINOIS 60532  
PHONE: (630)271-0770 • EMAIL: ECIVIL.COM

DWG LOCATION: H:\04-PH\3004\PLANS-ENG\REV-1

DRAWN BY: CJS/CMM FLD. BK. / PG. NO. : .

COMPLETION DATE: 4/26/06 JOB NO.: 04-PH-3004

HARLEM AVENUE MEDIAN IMPROVEMENTS

### SUMMARY OF QUANTITIES

DATE	REVISIONS	BY	SHEET
1 6/1/06	PER IDOT 5/18/06	OSC	<b>3</b> OF 31 SHEETS
2 8/8/06	PER IDOT 8/8/06	OSC/cmm	
3 9/27/06	PER IDOT 9/27/06	OSC	