



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 9, 2006

SUBJECT: FAU Route 1441 (Wilson Street)
Project ACBRM-ACTE-HD-7003(949)
Section 00-00059-00-BR (Batavia)
Kane County
Contract No. 83869
Item 44
November 17, 2006 Letting
Addendum (B)

TO PROSPECTIVE BIDDERS:

In accordance with your request, we have sent you plans and/or a proposal for the subject improvement.

To clarify information it is necessary to revise the following:

Proposal – Add page 98. (Inadvertently missing from original copy)

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

UNDER ROADWAYS AND SIDEWALKS and the applicable requirements of Article 550.07 of the Standard Specifications

All material removed shall become the property of the Contractor. The salvage value of this material shall be reflected in the unit price bid.

Measurement: Sanitary sewer removal will be measured for payment in feet, measured as removed.

Trench backfill will be measured for payment as specified in Article 208.03 of the Standard Specifications.

Excavation in rock will be measured for payment as specified in Article 502.14 of the Standard Specifications for Rock Excavation for Structures.

Basis of Payment: This work will be paid for at the contract unit price per foot for SANITARY SEWER REMOVAL 8", which price shall include all excavation and backfilling, except in rock, maintaining temporary drainage, and all sheeting and shoring required.

Excavation in rock will be paid for as specified in Article 502.15 of the Standard Specifications.

Trench backfill will be paid for as specified in Article 208.03 of the Standard Specifications.

SANITARY MANHOLE, 4' DIAMETER, SPECIAL FRAME AND LID

Work under this item will be performed in accordance with the applicable portions of Section 602 of the Standard Specifications and the Standard Specifications for Water and Sewer Main Construction in Illinois except as herein modified, and as shown on the plans.

Description: This work shall consist of constructing sanitary manholes with frame and lids at the locations shown on the plans.

General: The precast reinforced concrete manhole sections shall be set in butyl rope and the lift lug holes shall be sealed watertight. The manholes shall be installed on a 6 inch thick compacted CA-6 cushion conforming to Article 1004.01 of the Standard Specifications.

Frames and lids for the manholes shall conform to East Jordan Casting No. 1020 or approved equal. The solid lid shall have concealed pickholes and a watertight gasket. The words "CITY OF BATAVIA" and "SANITARY SEWER" shall be cast into the lids. Chimney seals shall be installed on all sanitary sewer manholes. The chimney seals shall be Infa-Shield, Canusa or approved equal and shall be installed per the manufacturer's instructions.

The manholes shall have rubber gasketed couplings for all inlet and outlet pipes. Inverts shall be precast concrete conforming to the size and shape of the pipe or poured in place using Class SI concrete shaped and troweled for a smooth finish conforming to the size and shape of the pipe. The slope on the benches shall match the drop between sewers shown on the plans.

Added
11-9-06