


| CONTRACT NO. 83869 |
RAU	SECTION	COUNTY	TOTAL SHEET	
1441	00-00059-00-BR	KANE	154	16
STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID	PROJECT



DETAIL A
BITUMINOUS REMOVAL AND RESURFACING



ADJACENT TO PCC PAVEMENT



ADJACENT TO PCC BASE COURSE AND BITUMINOUS RESURFACING

COMB CONC CURB AND GUTTER, TYPE B-V12 DETAIL

NOTES:

- 1. THE BOTTOM SLOPE OF THE COMB CONC CURB AND GUTTER CONSTRUCTED ADJACENT TO THE NEW PAVEMENT SHALL BE THE SAME SLOPE AS THE SUB-BASE.
- THE LONGITUDINAL JOINT TIE BARS SHALL BE NO. 6 AT 24" CENTERS IN ACCORDANCE WITH DETAILS FOR LONGITUDINAL CONSTRUCTION JOINT SHOWN ON STANDARD 420001.
- 3. 2 NO. 5 REBARS CONTINUOUS AND 2 3/4" DOWEL BARS WITH GREASE CAPS AT EACH EXPANSION JOINT. PLACE 3/4" EXPANSION JOINTS AT 100' INTERVALS, 5' 10' EITHER SIDE OF STRUCTURES, P.C.'S, AND RADIUS POINTS. SAW CONTRACTION JOINTS EVERY 10' BETWEEN EXPANSIONS TO THE DEPTH OF 3" WITHIN 24 HOURS OF PLACEMENT.

REVISIONS
NAME DATE

WILSON STREET

PAVEMENT DETAILS

SCALE: NTS DRAWN BY RVM
DATE 07/28/2006 CHECKED BY AKK

PLOT DATE * 7/25/2006 TIZED NAME * 172009\$Civil@Darpavementde401.dgn PLOT SCALE * \$SCALE\$ USER NAME * \$USER\$