

SCHEDULE OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 5	04-00163-00-BR	STEPHENSON	29	3
ILLINOIS				

CONTRACT NO. 85391

35101400 AGGREGATE BASE COURSE, TYPE B

LOCATION	TON
LT. STA. 253+30.81 TO LT. STA. 254+56.69	= 24
RT. STA. 253+30.81 TO RT. STA. 254+44.31	= 34
RT. STA. 256+03.31 TO RT. STA. 257+54.19	= 29
LT. STA. 256+15.69 TO LT. STA. 257+54.19	= 42
STA. 254+42 TO STA. 254+51.67	= 17
STA. 256+08.33 TO STA. 256+18	= 18
TOTAL	= 164 TON

48101200 AGGREGATE SHOULDERS, TYPE B

LOCATION	TON
LT. STA. 252+50.00 TO LT. STA. 253+30.81	= 12
RT. STA. 252+50.00 TO RT. STA. 253+30.81	= 15
LT. STA. 257+54.19 TO LT. STA. 258+00.00	= 8
RT. STA. 257+54.19 TO RT. STA. 258+00.00	= 8
TOTAL	= 43 TON

40500100 BITUMINOUS MATERIALS (PRIME COAT)

LOCATION	GALLON
LT. STA. 253+30.81 TO LT. STA. 254+56.69	= 25
RT. STA. 253+30.81 TO RT. STA. 254+44.31	= 35
RT. STA. 256+03.31 TO RT. STA. 257+54.19	= 30
LT. STA. 256+15.69 TO LT. STA. 257+54.19	= 43
STA. 254+42 TO STA. 254+51.67	= 8
STA. 256+08.33 TO STA. 256+18	= 8
STA. 252+50.00 TO STA. 254+42.11	= 47
STA. 256+18.03 TO STA. 258+00.00	= 45
TOTAL	= 241 GALLON

63200305 STEEL PLATE BEAM GUARDRAIL REMOVAL

LOCATION	FOOT
NORTHWEST CORNER EXISTING STRUCTURE	= 50
SOUTHWEST CORNER EXISTING STRUCTURE	= 62.5
NORTHEAST CORNER EXISTING STRUCTURE	= 62.5
SOUTHEAST CORNER EXISTING STRUCTURE	= 50
TOTAL	= 225 FOOT

40500300 BITUMINOUS MIXTURE COMPLETE

LOCATION	TON
LT. STA. 253+30.81 TO LT. STA. 254+56.69	= 12
RT. STA. 253+30.81 TO RT. STA. 254+44.31	= 17
RT. STA. 256+03.31 TO RT. STA. 257+54.19	= 14
LT. STA. 256+15.69 TO LT. STA. 257+54.19	= 21
STA. 252+50.00 TO STA. 254+51.67	= 122
STA. 256+08.33 TO STA. 258+00.00	= 81
TOTAL	= 267 TON

63200307 STEEL PLATE BEAM GUARDRAIL REMOVAL ATTACHED TO STRUCTURE

LOCATION	FOOT
LT. STA. 254+70 TO LT. STA. 255+90	= 120
RT. STA. 254+70 TO RT. STA. 255+90	= 120
TOTAL	= 240 FOOT

40600980 BITUMINOUS SURFACE REMOVAL - BUTT JOINT

LOCATION	SQ YD
STA. 252+50.00 TO STA. 252+89.00	= 95
STA. 257+00.00 TO STA. 258+00.00	= 245
TOTAL	= 340 SQ YD

78001110 PAINT PAVEMENT MARKING - LINE 4"

LOCATION	FOOT
LT. & RT. STA. 252+50 TO LT. & RT. STA. 258+00 (WHITE SOLID)	= 1100
@ STA. 252+50 TO @ STA. 258+00 (YELLOW SKIP DASH)	= 140
W.B. @ STA. 252+50 TO W.B. @ 256+10 (YELLOW SOLID)	= 360
TOTAL	= 1600 FOOT

44000100 PAVEMENT REMOVAL

LOCATION	SQ YD
STA. 254+42 TO STA. 254+70.00	= 68.5
STA. 255+90.00 TO STA. 256+18	= 68.5
TOTAL	= 137 SQ YD

TEMPORARY EROSION CONTROL

THE FOLLOWING QUANTITIES ARE ESTIMATES ONLY. ACTUAL QUANTITIES AND LOCATIONS FOR EROSION CONTROL WILL BE DETERMINED BY THE ENGINEER IN THE FIELD AND THERE WILL BE NO ADJUSTMENT IN ANY PRICE DUE TO A CHANGE IN PLAN QUANTITY.

PERIMETER EROSION BARRIER	= 935 FOOT
TEMPORARY EROSION CONTROL SEEDING	= 30 POUND

SCHEDULE OF QUANTITIES

SECTION 04-00163-00-BR
F.A.S. ROUTE 60 - C.H. 5
STEPHENSON COUNTY
STATION 255+30

4440 ASH GROVE
SPRINGFIELD, IL 62711
(217) 793-8600
oasinc@insightbb.com

OZYURT AND STONE, INC.
CONSULTING ENGINEERS

DRAWN: S.A.P.
DATE: 01/30/06

CHECKED: G.J.C.
DATE: 02/08/06

JOB NO.: 0527
FILE: 0527SCHED.DGN
DATE: 03/07/06