

80% FED
10% ST 10% CITY

80% FED
10% ST 10% CITY

RTE NO. FA 646	SECTION Y1W-1, RS-3	COUNTY PEORIA	TOTAL 142	SHEET # 6
-------------------	------------------------	------------------	--------------	--------------

CODE NUMBER	SUMMARY OF QUANTITIES ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				1000-2A 80% FED 20% ST ROADWAY	Y031-1F TRAFFIC SIGNALS
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2		2
89502380	REMOVE EXISTING HANDHOLE	EACH	1		1
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	7	***1	6
MX355150	BITUMINOUS BASE COURSE SUPERPAVE, 150MM	SQ M	212	212	
MX355200	BITUMINOUS BASE COURSE SUPERPAVE, 200MM	SQ M	6769	6769	
MX355030	BITUMINOUS BASE COURSE SUPERPAVE	M TON	263	263	
MX356370	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 200MM	SQ M	65	65	
MX356450	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 250 MM	SQ M	33	33	
MX406M20	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	M TON	1028	1028	
MX406024	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	M TON	2353	2353	
MX406216	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	M TON	2516	2516	
MX407440	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 290MM	SQ M	4900	4900	
MX407450	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 300MM	SQ M	19,435	19,435	
M4822000	BITUMINOUS SHOULDERS, SUPERPAVE	M TON	813	813	
MX482280	BITUMINOUS SHOULDERS SUPERPAVE 150MM	SQ M	917	917	
MX482330	BITUMINOUS SHOULDERS SUPERPAVE 200MM	SQ M	4353	4353	
MZ022800	FENCE REMOVAL	METER	98	98	
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1	
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1	
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1	1	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0076600	TRAINEES	HOUR	500	500	
X0323481	VIDEO VEHICLE DETECTION SYSTEM, 4 CAMERAS	EACH	2		2
X0329858	REMOVE AND REINSTALL EXISTING LUMINAIRE	EACH	1		1
MX033695	SANITARY SEWER, PVC SDR 26, 200MM, LESS THAN 1.8M DEPTH	METER	41	41	
MX033696	SANITARY SEWER, PVC SDR 26, 200MM, 1.8M TO 2.4M DEPTH	METER	48	48	
MX033697	SANITARY SEWER, PVC SDR 26, 200MM, 2.4M TO 3.0M DEPTH	METER	15	15	
MX033698	SANITARY SEWER, PVC SDR 26, 200MM, 3.0M TO 3.6M DEPTH	METER	7	7	
MX033699	SANITARY SEWER, PVC SDR 26, 200MM, 3.6M TO 4.5M DEPTH	METER	58	58	
MX033700	SANITARY SEWER, PVC SDR 26, 200MM, OVER 4.5M DEPTH	METER	28	28	
MX033701	SANITARY SEWER, DUCTILE IRON, 200MM, LESS THAN 1.8M DEPTH	METER	8	8	
MX033702	SANITARY SEWER, DUCTILE IRON, 200MM, 1.8M TO 2.4M DEPTH	METER	21	21	
MX033703	SANITARY SEWER, DUCTILE IRON, 200MM, 3.6M TO 4.5M DEPTH	METER	6	6	

* SPECIALTY ITEM ** Y080

CODE NUMBER	SUMMARY OF QUANTITIES ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				1000-2A 80% FED 20% ST ROADWAY	Y031-1F TRAFFIC SIGNALS
MX033704	MANHOLE TY A, 1.2M DIA. W / FR & LID	EACH	6	6	
X0325594	DROP MANHOLE CONNECTION	EACH	1	1	
MX033706	ADDITIONAL DEPTH OF MANHOLES	METER	4	4	
MX033707	SERVICE LATERALS, 150MM	METER	82	82	
MX033708	SERVICE LATERAL DIRECTIONAL BORE	METER	19	19	
MX033709	SERVICE TEE, 200MM X 200MM X 150MM	EACH	3	3	
MX033710	STEEL CASING PIPE AUGERED AND JACKED, 600MM	METER	22	22	
MX033711	CAP, 150MM	EACH	2	2	
MX033712	SEWER CLEANOUT, 150MM	EACH	2	2	
X0325595	SAMPLING ACCESS STRUCTURE	EACH	1	1	
MX033714	BITUMINOUS PAVEMENT REPLACEMENT (SERVICES)	SQ M	21	21	
MX033715	AGGREGATE SURFACE REPLACEMENT (SERVICES)	SQ M	15	15	
MX033716	BEDDING AND HAUNCHING	CU M	53	53	
MX033717	BEDDING AND HAUNCHING (SERVICES)	CU M	15	15	
MX033718	INITIAL BACKFILL	CU M	94	94	
MX033719	INITIAL BACKFILL (SERVICES)	CU M	35	35	
MX033720	SELECT GRANULAR BACKFILL (SERVICES)	CU M	36	36	
MX033705	DEFLECTION TESTING	METER	198	198	
X0325596	AIR TESTING	EACH	4	4	
67100100	MOBILIZATION	L SUM	1	1	

• SPECIALTY ITEMS
 ** CONSTRUCTION TYPE CODE Y080
 *** CONSTRUCTION TYPE CODE Y030-1E
 † REFER TO THE JOINT CITY OF PEORIA - STATE AGREEMENT DATED _____ FOR MONETARY PARTICIPATION OF EACH PARTY.

0-3

REVISIONS	
NAME	DATE
MMA, PJC	9/13/08

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 DATE: 09/01/08
 DRAWN BY: JDU
 CHECKED BY: ECM