

| | | | | |
|-----------------------|-----------|---------------------------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 332 | 88-1-88-1 | VERMILION | 140 | 2 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. 1 | | ILLINOIS FED. AID PROJECT | | |

INDEX OF SHEETS

| | |
|---|---------|
| COVER SHEET | 1 |
| HIGHWAY STANDARDS/INDEX OF SHEETS | 2 |
| GENERAL NOTES | 3-4 |
| SUMMARY OF QUANTITIES | 5-7 |
| EXISTING TYPICAL CROSS SECTIONS | 8-9 |
| PROPOSED TYPICAL CROSS SECTIONS | 10-13 |
| SCHEDULE OF QUANTITIES | 14-16 |
| TIE POINT SHEETS | 17-18 |
| US 136 PLAN SHEETS | 19-21 |
| US 136 PROFILE SHEETS | 22-23 |
| OLD SEATON HILL RD. PLAN & PROFILE SHEET | 24 |
| TEMPORARY ACCESS RD. PLAN & PROFILE SHEET | 25 |
| P.E. 2 & 3 PLAN & PROFILE SHEET | 26 |
| P.E. 1 PLAN & PROFILE SHEET | 27 |
| US 136 REMOVAL PLAN SHEETS | 28-30 |
| TRAFFIC CONTROL PLAN FOR MARKED ROAD CLOSED DETOUR | 31 |
| TEMPORARY TRAFFIC SIGNAL INSTALLATION SHEET | 32 |
| US 136 EROSION CONTROL PLAN SHEETS | 33-35 |
| OLD SEATON HILL RD. EROSION CONTROL & SEEDING PLAN SHEET | 36 |
| US 136 SEEDING PLAN SHEETS | 37-39 |
| R. O. W. PLANS | 40-41 |
| STRUCTURE PLANS | 42-72 |
| DETAIL OF TREE PLANTING | 73 |
| DETAIL OF POROUS GRANULAR BACKFILL AT A. R. PIPE CULVERTS | 73 |
| TYPICAL DETAIL OF RURAL PRIVATE AND COMMERCIAL ENTRANCES | 74 |
| TYPICAL APPLICATION OF TRAF CONT DEVICES FOR ROAD CLOSURE | 74 |
| DETAIL OF TEMPORARY RUMBLE STRIP LAYOUT AT BOWMAN AVE | 75 |
| PIPE CULVERT DETAIL - STA. 194+07.41 | 75 |
| DETAIL OF PROFILE CHANGE US-136 | 75 |
| TYPICAL APPLICATIONS OF PAVEMENT MARKINGS AND MARKERS | 76-79 |
| US 136 MAINLINE CROSS SECTIONS | 80-109 |
| P.E. 3 CROSS SECTIONS | 110-111 |
| P.E. 2 CROSS SECTIONS | 112-116 |
| P.E. 1 CROSS SECTIONS | 117-120 |
| OLD SEATON HILL RD. CROSS SECTIONS | 121-134 |
| TEMPORARY ACCESS RD. CROSS SECTIONS | 135-140 |

LIST OF STANDARDS

| | |
|-----------|--|
| 280001-02 | TEMPORARY EROSION CONTROL SYSTEMS |
| 420401-05 | BRIDGE APPROACH PAVEMENT |
| 482001 | BITUMINOUS SHOULDER ADJACENT TO FLEXIBLE PAVEMENT |
| 515001-02 | NAME PLATE FOR BRIDGES |
| 542101 | REINFORCED CONCRETE END SECTIONS 375mm (15") THRU 900mm (36") AT RIGHT ANGLES WITH ROADWAY |
| 542401 | METAL END SECTIONS FOR PIPE CULVERTS |
| 602306 | INLET - TYPE B |
| 602601 | PRECAST REINFORCED CONCRETE FLAT SLAB TOP |
| 610001-02 | SHOULDER INLET WITH CURB |
| 630001-06 | STEEL PLATE BEAM GUARDRAIL |
| 630301-03 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS |
| 631031-05 | TRAFFIC BARRIER TERMINAL, TYPE 6 |
| 635006-02 | REFLECTOR AND TERMINAL MARKER PLACEMENT |
| 635011-01 | REFLECTOR MARKER AND MOUNTING DETAILS |
| 664001-01 | CHAIN LINK FENCE |
| 666001 | RIGHT-OF-WAY MARKERS |
| 667101 | PERMANENT SURVEY MARKERS |
| 701006-02 | OFF-RD OPERATIONS, 2L, 2W, 4.5 m (15') TO 600 mm (24") FROM PAVEMENT EDGE |
| 701201-02 | LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH |
| 701301-02 | LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS |
| 702001-06 | TRAFFIC CONTROL DEVICES |
| 780001-01 | TYPICAL PAVEMENT MARKINGS |
| 781001-02 | TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS |
| 880001 | SPAN WIRE MOUNTED SIGNALS AND FLASHING BEACON INSTALLATION |
| 000001-04 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 001001 | AREAS OF REINFORCEMENT BARS |
| 001006 | DECIMAL OF AN INCH AND OF A FOOT |

PLOT DATE: 8/26/2008
 PLOT SCALE: 1/8" = 1'-0"
 USER NAME:

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|---------------------------------------|
| NAME | DATE | |
| | | INDEX OF SHEETS/LIST OF STANDARDS |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

SCALE: VERT. DATE HORIZ. DRAWN BY CHECKED BY