

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	RX-1-BR-1	VERMILION	140	16
STA. _____ TO STA. _____		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

POLYUREA PAVEMENT MARKING TYPE II, LINE 4" - 78008310

STATION	TO	STATION	FOOT
196+22.82		201+04.68	963.8

WHITE

196+22.82		201+04.68	120.5
			TOTAL = 1084.3
			TOTAL = 1085.0 FOOT

2-WAY AMBER RAISED REFLECTIVE PAVEMENT MARKER - 78100100

STATION	TO	STATION	EACH
186+00.00		196+22.82	14.0
201+04.68		202+00.00	1.0
			TOTAL = 15.0 EACH

2-WAY AMBER RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) - 78100105

STATION	TO	STATION	EACH
196+22.82		201+04.68	6.0
			TOTAL = 6.0 EACH

GUARDRAIL MARKERS, TYPE A - 78200410

STATION	TO	STATION	EACH
190+89.80		196+60.45	7.0
201+00.62		201+96.27	2.0
195+81.23		196+26.88	4.0
200+67.05		202+02.05	2.0
			TOTAL = 15.0 EACH

BARRIER WALL MARKERS, TYPE B - 78200520

STATION	TO	STATION	EACH
196+60.45		201+00.62	6.0
196+26.88		200+67.05	6.0
			TOTAL = 12.0 EACH

TERMINAL MARKER - DIRECT APPLIED - 78201000

STATION	EACH
190+52.30	1.0
195+43.73	1.0
TOTAL = 2.0 EACH	

RAISED REFLECTIVE PAVEMENT MARKER, REMOVAL - 78300200

STATION	TO	STATION	EACH
186+00.00		202+00.00	16.0
			TOTAL = 16.0 EACH

EVERGREEN, PICEA PUNGENS (COLORADO SPRUCES), 6' HEIGHT, BALLED AND BURLAPPED - D2002172

PARCEL #	EACH
5644003	12.0
TOTAL = 12.0 EACH	

PIPE DRAIN REMOVAL - X0323586

STATION	O/S	TO	O/S	FOOT
199+95.84	16.73		54.67	37.9
199+76.26	16.11		64.27	48.2
				TOTAL = 86.1
				TOTAL = 86.0

DIAMOND GRINDING (BRIDGE SECTION) - X0324865

STATION	TO	STATION	SQ YD
194+22.82		195+22.82	444.4
201+14.63		202+14.67	444.4
195+22.82		196+22.82	444.4
201+04.68		201+14.67	44.4
196+22.82		196+52.82	133.3
200+74.68		201+04.68	133.3
			1976.0
			TOTAL = 3620.2
			TOTAL = 3620.0 SQ YD

AGGREGATE DITCH CHECK - X0348700

STATION	O/S	EACH
191+71.88	39.7	1.0
		TOTAL = 1.0 EACH

TEMPORARY DITCH CHECKS, AGGREGATE - X2800110

STATION	O/S	EACH
LT 185+96.93	29.1	1.0
LT 186+68.62	28.6	1.0
LT 187+48.40	29.6	1.0
LT 188+28.19	30.4	1.0
LT 189+07.98	32.2	1.0
LT 189+96.69	35.3	1.0
LT 190+71.99	39.9	1.0
LT 191+03.72	39.9	1.0
RT 186+86.23	32.2	1.0
RT 187+58.54	32.6	1.0
RT 188+45.39	32.9	1.0
RT 189+65.12	32.5	1.0
RT 191+15.00	37.2	1.0
RT 192+25.00	49.9	1.0
RT 193+50.00	53.1	1.0
RT 195+75.00	54.9	1.0
		TOTAL = 16.0 EACH

TEMPORARY ACCE (PRIVATE ENTRANCE) - X4021000

STATION	O/S	EACH
190+31.19		1.0
		TOTAL = 1.0 EACH

CONCRETE HEADWALL REMOVAL SPECIAL - X5012650

STATION	O/S	EACH
193+07.41	45.0	1.0
		TOTAL = 1.0 EACH

PLOT DATE = 8/26/2006
 FILE NAME = c:\projects\9593196\081\text2.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = stults,j

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. / HORIZ.
 DATE

DRAWN BY
 CHECKED BY