

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
583	****	SCHUYLER	56	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT **	
**** SECTION 02-00067-00-BR				
** BRS-583(111)				

PAVEMENT SCHEDULE											
LOCATION	35100100 AGGREGATE BASE COURSE, TYPE A (TON)	35101400 AGGREGATE BASE COURSE, TYPE B (TON)	40600100 BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	40600300 AGGREGATE (PRIME COAT) (TON)	40600990 TEMPORARY RAMP (SQ YD)	40800010 BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	42001400 BRIDGE APPROACH PAVEMENT (SPECIAL) (SQ YD)	X3560130 BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH (SQ YD)	X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50 (TON)	X4066614 BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50 (TON)	XX004949 INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE (TON)
STA. 48+80 TO STA. 48+85					13						
STA. 48+80 TO STA. 52+38.86			576	5				75			
STA. 49+64 TO STA. 52+38.86									159		
STA. 50+21 TO STA. 50+93	60										
STA. 50+93 TO STA. 52+38.86	235										
STA. 51+46 RT, F.E.											23
STA. 51+84 LT, F.E.											13
STA. 52+33.86 TO STA. 52+38.86					13						
STA. 52+39.04 TO STA. 52+69.04							105				
STA. 57+13 RT TO STA. 62+50 RT								227			
STA. 57+22.46 TO STA. 52+52.46							105				
STA. 57+52.64 TO STA. 57+57.64					13						
STA. 57+52.64 TO STA. 59+95	390										
STA. 57+52.64 TO STA. 61+31									217		
STA. 57+52.64 TO STA. 62+50			799	7				105			
STA. 59+84 LT, F.E.		59									14
STA. 59+95 TO STA. 60+49	45										
STA. 62+45 TO STA. 62+50					13						
TOTALS	730	320	1375	12	52	160	210	227	180	376	50

SHOULDER SCHEDULE		
LOCATION	48101200 AGGREGATE SHOULDERS, TYPE B (TON)	48202400 BITUMINOUS SHOULDERS, SUPERPAVE, 6" (SQ YD)
STA. 48+70 LT TO STA. 51+54 LT	46	
STA. 48+73 LT TO STA. 52+36 LT		162
STA. 48+86 RT TO STA. 52+42 RT		159
STA. 48+88 RT TO STA. 51+18 RT	37	
STA. 51+71 RT TO STA. 52+72 RT	25	
STA. 51+96 LT TO STA. 52+65 LT	11	
STA. 57+19 LT TO STA. 59+60 LT	41	
STA. 57+27 RT TO STA. 62+50 RT	84	
STA. 57+49 LT TO STA. 62+50 LT		223
STA. 57+55 RT TO STA. 62+50 RT		220
STA. 59+96 LT TO STA. 62+50 LT	46	
TOTALS	290	764

TEMPORARY BARRIER SCHEDULE				
LOCATION	70400100 TEMPORARY CONCRETE BARRIER (FOOT)	70400200 RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
STA. 47+20 LT TO STA. 47+50 LT (STAGE 1)			1	
STA. 47+20 RT TO STA. 47+50 RT (STAGE 2)				1
STA. 47+60 TO STA. 62+73 (STAGE 1)	1512.5			
STA. 47+60 TO STA. 62+73 (STAGE 2)		1512.5		
STA. 62+75 LT TO STA. 63+05 LT (STAGE 1)			1	
STA. 62+75 RT TO STA. 63+05 RT (STAGE 2)				1
TOTALS	1512.5	1512.5	2	2

SEEDING SCHEDULE					
LOCATION	25000300 SEEDING, CLASS 3 (ACRE)	25000400 NITROGEN FERTILIZER NUTRIENT (POUND)	25000500 PHOSPHORUS FERTILIZER NUTRIENT (POUND)	25000600 POTASSIUM FERTILIZER NUTRIENT (POUND)	25100115 MULCH, METHOD 2 (ACRE)
STA. 48+57 LT TO STA. 54+54 LT	1.46	132	132	132	1.46
STA. 48+90 RT TO STA. 54+76 RT	0.97	88	88	88	0.97
STA. 55+16 LT TO STA. 62+50 LT	1.07	97	97	97	1.07
STA. 55+37 RT TO STA. 62+50 RT	0.85	77	77	77	0.85
TOTALS	4.35	394	394	394	4.35

PLOT DATE = 9/25/2006
FILE NAME = J:\02157\DRAWINGS\02157SCH.dgn
PLOT SCALE = 5/8"=1'-0"
REFERENCE = .REF.
OPERATOR =

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
FAS 583 (CHS) OVER LAMOINE RIVER
SECTION 02-00067-00-BR
SCHUYLER COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE 5/13/06

DRAWN BY SUTHEARD
CHECKED BY BOTT

GREENE & BRADFORD, INC.
OF SPRINGFIELD
REGISTERED PROFESSIONAL ENGINEERS
ILLINOIS LICENSE NO. 021-000000-000000
021-000000-000000-000000

COMPUTER FILE NO. 02157SCH
PROJECT 02157
9/22/06-MDS

SCHEDULE OF QUANTITIES