

-INDEX TO SHEETS-

- 1 COVER SHEET/SUMMARY OF QUANTITIES
- 2 GENERAL NOTES / TABULATION OF QUANTITIES
- 3-4 TYPICAL SECTIONS
- 5-8 PLAN & PROFILE
- 9 DETAILS

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
PLANS FOR PROPOSED  
FEDERAL AID PROJECT  
FAU 9333

NORTH 29TH STREET  
SECTION 05-00215-00-RS  
PROJECT NO. M - 5011 (220)  
CITY OF EAST ST. LOUIS  
ST. CLAIR COUNTY  
JOB NO. C-98-374-06

SECTION NO.	COUNTY HIGHWAY	COUNTY	SHEET OF SHEETS
05-00215-00-RS	N/A	ST. CLAIR	1 OF 9
ILLINOIS		FEDERAL AID PROJECT	
CONTRACT NO. 97283			

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	775
40600300	AGGREGATE (PRIME COAT)	TON	15
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	130
40600990	TEMPORARY RAMP	SQ YD	143
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	19
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	244
42400800	DETECTABLE WARNINGS	SQ FT	24
44000035	BITUMINOUS SURFACE REMOVAL	SQ YD	4397
44000600	SIDEWALK REMOVAL	SQ FT	217
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	277
44200905	CLASS B PATCHES, TYPE II, 6 INCH	SQ YD	15
44200911	CLASS B PATCHES, TYPE IV, 6 INCH	SQ YD	525
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	24
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	2172
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2990
60255500	MANHOLES TO BE ADJUSTED	EACH	3
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	420
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	70
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5308
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	31
X0323095	TYPE 1 FRAME, CLOSED LID	EACH	2
X0324554	CONCRETE FLAT SLAB TOP	EACH	2
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	6
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	650
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	191
X440A200	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING)	SQ YD	239
X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	439
XX004949	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	8
Z0010615	CLEANING EXISTING INLETS	EACH	5
Δ Z0076600	TRAINEES	HOURL	500

\* SPECIALTY ITEMS

Δ Y080

STANDARDS

000001-04	701311-02
424001-04	701501-03
442101-05	701801-03
602601	702001-06
604001-02	780001-01
606001-02	781001-02
701301-02	

DESIGN DESIGNATION  
ROADWAY CLASSIFICATION : LOCAL ROAD  
CURRENT ADT (2007) = 1770 VPD  
REGULATORY SPEED = 25 MPH

Call Joint Utility Locating Information for Excavators  
(J.U.L.I.E.) before digging 800-892-0123

EAST ST. LOUIS TOWNSHIP  
SEC 19&20, T.2N., R.9W.

PLAN: 1"=40'  
PROFILE: 1"=40' HORIZ.  
1"=5' VERT.

