

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
821	(15-2)BR	JEFFERSON	33
STA. TO STA.			4
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 98958			

SUMMARY OF QUANTITIES				S.N. 041-0027 80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	X071-2A	SFTY-3N
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CALL DA	12	12	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	176	176	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	54	54	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	490	490	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	470	470	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,920	1,920	
* 78100300	REPLACEMENT REFLECTOR	EACH	10	10	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	6	6	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	534	534	
X3560140	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 INCH	SQ YD	408	408	
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	39	39	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	1	
XX006345	TURBIDITY BARRIER	FOOT	200	200	
Z0002600	BAR SPLICERS	EACH	598	598	
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2		2
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2		2

* SPECIALTY ITEM

SUMMARY OF QUANTITIES				S.N. 041-0027 80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	X071-2A	SFTY-3N

SUMMARY OF QUANTITIES

F.A.P. ROUTE 821 (IL 15)
SECTION (15-2)BR
JEFFERSON COUNTY

CUMMINS ENGINEERING CORPORATION
JOB #: 2175
FILE: 21750TY
DATE: 6/01/06