CONTRACT NO. 98982

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	VARIOUS	21	5
STA. _____ TO STA. _____				
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

* D-9 SAFETY FY 07-1

SEEDING AND EROSION CONTROL SCHEDULE

LOCATION		SEEDING CLASS 2 (MODIFIED)	SEEDING CLASS 7 (TEMPORARY)	NITROGEN FERTILIZER NUTRIENTS		PHOSPHORUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2 FOR CLASS 2	MULCH METHOD 2 FOR CLASS 7	TEMPORARY DITCH CHECKS
				CLASS 2	CLASS 7						
		ACRE	ACRE	POUND	POUND	POUND	POUND	TON	ACRE	ACRE	EACH
PIER PROTECTION											
PULASKI COUNTY											
077-0031	MP 8.76	0.4	0.4	48	16	48	48	0.8	0.4	0.4	3
077-0034	MP 10.38	0.4	0.4	48	16	48	48	0.8	0.4	0.4	3
COUNTY TOTAL		0.8	0.8	96	32	96	96	1.6	0.8	0.8	6
WILLIAMSON COUNTY											
100-0040	MP 58.96	0.2	0.2	24	8	24	24	0.4	0.2	0.2	3
COUNTY TOTAL		0.2	0.2	24.0	8.0	24.0	24.0	0.4	0.2	0.2	3.0
FRANKLIN COUNTY											
028-0057	MP 72.99	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
028-0053	MP 75.49	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
028-0056	MP 76.51	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
028-0059	MP 77.52	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
028-0055	MP 80.67	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
COUNTY TOTAL		1.5	1.5	180.0	60.0	180.0	180.0	3.0	1.5	1.5	15.0
JEFFERSON COUNTY											
041-0055	MP 82.69	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
041-0054	MP 86.34	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
041-0058	MP 90.47	0.4	0.4	48	16	48	48	0.8	0.4	0.4	3
041-0051	MP 96.68	0.2	0.2	24	8	24	24	0.4	0.2	0.2	3
041-0053	MP 98.88	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
041-0057	MP 101.94	0.3	0.3	36	12	36	36	0.6	0.3	0.3	3
041-0056	MP 104.02	0.4	0.4	48	16	48	48	0.8	0.4	0.4	3
COUNTY TOTAL		2.2	2.2	264.0	88.0	264.0	264.0	4.4	2.2	2.2	21.0
CABLE BARRIER											
STATION 1542+00 TO STATION 1562+00		0.2	0.2	24	8	24	24	0.4	0.2	0.2	
STATION 1562+55 TO STATION 1572+91.1		0.1	0.1	12	4	12	12	0.2	0.1	0.1	
STATION 0+00 TO STATION 61+70		0.6	0.6	72	24	72	72	1.2	0.6	0.6	
STATION 67+00 TO STATION 165+50		0.9	0.9	108	36	108	108	1.8	0.9	0.9	
TOTALS		6.5	6.5	780	260	780	780	13.0	6.5	6.5	45
				1,040					13.0		

NOTES:
FOR THE CABLE BARRIER, SEEDING QUANTITIES ARE CALCULATED FOR A 4' STRIP ALONG THE ENTIRE INSTALLATION.
THE ACTUAL LOCATIONS SHALL BE AS DIRECTED BY THE ENGINEER.

PIER PROTECTION SCHEDULE

STRUCTURE NUMBER	MILE POST	STATION	COUNTY	SAND MODULE IMPACT ATTENUATOR	FURNISHED EXCAVATION	COMMENTS
				EACH	CU YD	
077-0031	MP 8.76	699+70.31	PULASKI	2		
077-0034	MP 10.38	613+74.05	PULASKI	2		
100-0040	MP 58.96	165+80	WILLIAMSON	2		
028-0057	MP 72.99	415+71.58	FRANKLIN	2		24" RCCP TO SOUTH
028-0053	MP 75.49	283+35.75	FRANKLIN	2		
028-0056	MP 76.51	229+54.5	FRANKLIN	2		GRATE TO THE SOUTH
028-0059	MP 77.52	176+52.10	FRANKLIN	2		24" RCCP TO NORTH
028-0055	MP 80.67	9+78.11	FRANKLIN	2		GRATE TO THE NORTH, UNDERDRAIN OUTLETS TO THE SOUTH
041-0055	MP 82.69	117+09.55	JEFFERSON	2	303	2-24" RCCP TO THE SOUTH
041-0054	MP 86.34	310+00	JEFFERSON	2	139	
041-0058	MP 90.47	527+90	JEFFERSON	2	335	UNDERDRAINS TO THE NORTH
041-0051	MP 96.68	881A+48	JEFFERSON	2	78	BUSHES TO BE REMOVED
041-0053	MP 98.88	996+50	JEFFERSON	2	248	DRAINAGE GRATE AND UNDERDRAIN TO NORTH, GUARDPOST REMOVAL
041-0057	MP 101.94	1157+11.29	JEFFERSON	2	344	DRAINAGE GRATE TO NORTH, BUSHES TO BE REMOVED
041-0056	MP 104.02	1267+84	JEFFERSON	2	188	
TOTALS				30	1635	

PLOT DATE = 8/21/2006
FILE NAME = c:\projects\d784108\d784108schun32
PLOT SCALE = 100.0000 ' / IN.
USER NAME = skapler-dgd