

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	VARIOUS	21	6
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		
* D-9 SAFETY FY 07-1				

RUMBLE STRIP SCHEDULE

LOCATION MILEPOST TO MILEPOST	RUMBLE STRIP FOOT	REMARKS
FAI 57		
NB LANES		
OUTSIDE SHOULDER MP 20.75 TO MP 22.01	6653	
MEDIAN SHOULDER MP 20.75 TO MP 22.01	6653	
SB LANES		
OUTSIDE SHOULDER MP 20.75 TO MP 22.01	6653	
MEDIAN SHOULDER MP 20.75 TO MP 22.01	6653	
COUNTY TOTAL:	26,612	
UNION COUNTY		
FAI 57		
NB LANES		
OUTSIDE SHOULDER MP 22.01 TO MP 39.02	82,439	GAP SN 091-0001 (121') GAP EXIT RAMP AT DONGOLA INTERCHANGE (528') GAP SN 091-0004 (339') GAP ENTRANCE RAMP AT DONGOLA INTERCHANGE (900') GAP SN 091-0005 (195'), SN 091-0007 (210'), SN 091-0009 (175') GAP EXIT RAMP AT IL 146 INTERCHANGE (450') GAP SN 091-0011 (137') GAP ENTRANCE RAMP AT IL 146 INTERCHANGE (800') GAP EXIT RAMP AT TRAIL OF TEARS REST AREA (530') GAP ENTRANCE RAMP AT TRAIL OF TEARS REST AREA (1050') GAP SN 091-0013 (192'), SN 091-0015 (127') GAP EXIT RAMP AT LICK CREEK INTERCHANGE (580') GAP ENTRANCE RAMP AT LICK CREEK INTERCHANGE (800') GAP SN 091-0017 (240') TOTAL LENGTH TO BE GAPPED FOR OUTSIDE SHOULDER = 7374'
MEDIAN SHOULDER MP 22.01 TO MP 39.02	88,077	GAP SN 091-0001 (121'), SN 091-0004 (339'), SN 091-0005 (195'), SN 091-0007 (210'), SN 091-0009 (175'), SN 091-0011 (137'), SN 091-0013 (192'), SN 091-0015 (127'), SN 091-0017 (240') TOTAL LENGTH TO BE GAPPED FOR MEDIAN SHOULDER = 1736'
SB LANES		
OUTSIDE SHOULDER MP 22.01 TO MP 39.02	81,830	GAP SN 091-0002 (121') GAP ENTRANCE RAMP AT DONGOLA INTERCHANGE (850') GAP SN 091-0003 (339') GAP EXIT RAMP AT DONGOLA INTERCHANGE (460') GAP SN 091-0006 (167') GAP ENTRANCE RAMP AT US 51 INTERCHANGE (680') GAP SN 091-0008 (210'), SN 091-0010 (175') GAP ENTRANCE RAMP AT IL 146 INTERCHANGE (885') GAP SN 091-0012 (137') GAP EXIT RAMP AT IL 146 INTERCHANGE (440') GAP ENTRANCE RAMP AT TRAIL OF TEARS REST AREA (1050') GAP EXIT RAMP AT TRAIL OF TEARS REST AREA (530') GAP SN 091-0014 (192'), SN 091-0016 (127') GAP ENTRANCE RAMP AT LICK CREEK INTERCHANGE (800') GAP EXIT RAMP AT LICK CREEK INTERCHANGE (580') GAP SN 091-0018 (240') TOTAL LENGTH TO BE GAPPED FOR OUTSIDE SHOULDER = 7983'
MEDIAN SHOULDER MP 22.01 TO MP 39.02	88,105	GAP SN 091-0002 (121'), SN 091-0003 (339'), SN 091-0006 (167'), SN 091-0008 (210'), SN 091-0010 (175'), SN 091-0012 (137'), SN 091-0014 (192'), SN 091-0016 (127'), SN 091-0018 (240') TOTAL LENGTH TO BE GAPPED FOR MEDIAN SHOULDER = 1708'
COUNTY TOTAL:	340,451	

LOCATION MILEPOST TO MILEPOST	RUMBLE STRIP FOOT	REMARKS
FAI 57		
NB LANES		
OUTSIDE SHOULDER MP 39.02 TO MP 43.27	21,060	GAP EXIT RAMP AT GOREVILLE INTERCHANGE (580') GAP ENTRANCE RAMP AT GOREVILLE INTERCHANGE (800') TOTAL LENGTH TO BE GAPPED FOR OUTSIDE SHOULDER = 1380'
MEDIAN SHOULDER		
MP 39.02 TO MP 43.27	22,440	
SB LANES		
OUTSIDE SHOULDER MP 39.02 TO MP 43.27	21,060	GAP ENTRANCE RAMP AT GOREVILLE INTERCHANGE (800') GAP EXIT RAMP AT GOREVILLE INTERCHANGE (580') TOTAL LENGTH TO BE GAPPED FOR OUTSIDE SHOULDER = 1380'
MEDIAN SHOULDER		
MP 39.02 TO MP 43.27	22,440	
COUNTY TOTAL:	87,000	
WILLIAMSON		
FAI 57		
NB LANES		
OUTSIDE SHOULDER MP 43.27 TO MP 50.55	33,188	GAP EXIT RAMP AT FAI 24 INTERCHANGE (656') GAP ENTRANCE RAMP AT FAI 24 INTERCHANGE (1220') GAP EXIT RAMP AT IL 148 INTERCHANGE (580') GAP ENTRANCE RAMP AT IL 148 INTERCHANGE (830') GAP EXIT RAMP AT WEIGH STATION (595') GAP ENTRANCE RAMP AT WEIGH STATION (1370') TOTAL LENGTH TO BE GAPPED FOR OUTSIDE SHOULDER = 5251'
MEDIAN SHOULDER		
MP 43.27 TO MP 50.55	38,439	
SB LANES		
OUTSIDE SHOULDER MP 43.27 TO MP 62.10	80,528	GAP ENTRANCE RAMP AT FAI 24 INTERCHANGE (1000') GAP EXIT RAMP AT FAI 24 INTERCHANGE (2025') GAP EXIT RAMP AT IL 148 INTERCHANGE (580') GAP ENTRANCE RAMP AT WEIGH STATION (1370') GAP EXIT RAMP AT WEIGH STATION (400') GAP CRAB ORCHARD CREEK PROJECT (2500') GAP OLD IL13 & IL 13 INTERCHANGE PROJECT (6920') GAP LAKE CREEK-JOHNSTON CITY INTERCHANGE PROJECT (4100') TOTAL LENGTH TO BE GAPPED FOR OUTSIDE SHOULDER = 18,895'
MEDIAN SHOULDER		
MP 43.27 TO MP 62.10	85,903	GAP CRAB ORCHARD CREEK PROJECT (2500') GAP OLD IL13 & IL 13 INTERCHANGE PROJECT (6920') GAP LAKE CREEK-JOHNSTON CITY INTERCHANGE PROJECT (4100') TOTAL TO BE GAPPED FOR MEDIAN SHOULDER = 13,520'
COUNTY TOTAL:	238,058	

PLOT DATE = 8/21/2006
 FILE NAME = c:\pvc\secta\p981065\p981066.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = shpaar-dgd