

DATE	
BY	
PLANNING	
DESIGNED	
CHECKED	
BY	
DATE	
NOTE BOOK	
NO.	
ADD FILE NAME	

DATE	
BY	
PROF FILE	
DESIGNED	
CHECKED	
BY	
DATE	
NOTE BOOK	
NO.	
STRUCTURE NOTATION USED	

FILE NAME = T:\16898B\Civil\6898B_Monroc_Surveys\Plotting\Print Export\016898B-int-500.dgn

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				90% FED 10% STATE ROADWAY	90% FED 10% STATE UTILITIES	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING	90% FED 10% STATE ROADWAY LIGHTING	
				0004 URBAN	0043 URBAN	0010 016-1700	0014 016-2017	0021 URBAN	0021 URBAN	
* X0326801	COMBINED SEWERS TO BE CLEANED	FOOT	310	310						
* X0327004	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	7					7		
* X0327236	TEMPORARY WOOD POLE, 50 FT., CLASS 4	EACH	13					13		
X0327267	SLOPE INCLINOMETER	EACH	0			2	4			
X0327348	COMBINED SEWER REMOVAL 10"	FOOT	96	96						
X0327357	CONSTRUCTION VIBRATION MONITORING	LSUM	1	1						
* X0327552	TREE GRATE REMOVAL	EACH	11	11						
* X0327607	FIBER OPTIC SPLICE-MAINLINE	EACH	2					2		
X0327615	COMBINED SEWER REMOVAL 8"	FOOT	39	39						
* X0327616	MAINTAINING ITS DURING CONSTRUCTION	CAL MO	21					21		
* X0327689	COMBINED SEWERS TO BE CLEANED, SPECIAL	FOOT	1231		1231					
* X0327965	ELECTRIC CABLE NO. 19 50-PAIR	FOOT	250					250		
* X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	32074	31432	642					
* X0370008	BREAKDOWN MANHOLE (CDOT)	EACH	2							2
* X0370049	UNDERGROUND CONDUIT, PVC, 2" DIA., SCHEDULE 80 (CDOT)	FOOT	95							95
* X0370068	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE (CDOT)	EACH	3							3
X0370069	COMBINED SEWER (EXTRA STRENGTH VIRTIFIED CLAY), 8 INCH (CDOT)	FOOT	53	53						
X0370070	COMBINED SEWERS, WATER MAIN REQUIREMENTS, 8 INCH (CDOT)	FOOT	33	33						
* X0370074	RACKING CABLES IN MANHOLE OR HANDHOLE (CDOT)	EACH	8							8
* X0370075	UNDERGROUND CONDUIT, PVC, 4" DIA., SCHEDULE 80 (CDOT)	FOOT	970					190		780
X0370080	COMBINATION CURB AND GUTTER TYPE B V.12 (CDOT)	FOOT	676	676						

* DENOTES SPECIALTY ITEM
 DENOTES NON-PARTICIPATING ITEM

REV 11-7-17

PARSONS BRINCKERHOFF

USER NAME = Kucharski	DESIGNED - MMA	REVISED -
DRAWN - MMA	CHECKED - RT	REVISED -
PLOT SCALE = NO SCALE	DATE - 07/14/2017	REVISED -
PLOT DATE = 7/13/2017		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 10 OF 14 SHEETS STA. TO STA.

F.A.I. RTE. 90/94	SECTION 2014-016R&B	COUNTY COOK	TOTAL SHEETS 378	SHEET NO. 15
CONTRACT NO. 60X95			[ILLINOIS] FED. AID PROJECT	

DATE	
BY	
PLAN	
SURVEYED	
PLOTTED	
CHECKED	
BY	
DATE	
NOTE BOOK NO.	
DATE	
FILE NAME	

DATE	
BY	
PROFILE	
SURVEYED	
PLOTTED	
CHECKED	
BY	
DATE	
NOTE BOOK NO.	
DATE	
FILE NAME	

FILE NAME = T:\1681081\Civil\60x95 Monroe Street\Plotting\Print Export\1681081-INT-500.dwg

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				90% FED ROADWAY	90% FED UTILITIES	90% FED BRIDGE	90% FED RETAINING WALL	90% FED HIGHWAY LIGHTING	90% FED ROADWAY LIGHTING
				0004 URBAN	0043 URBAN	0010 016-1700	0044 016-2017	0021 URBAN	0021 URBAN
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	21					21	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	361			211	150		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1		1				
Z0062456	TEMPORARY PAVEMENT	SQ YD	223	223					
∅ Z0076600	TRAINEES	HOUR	2000	2000					
∅ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	2000	2000					
* X1400249	LUMINAIRE, UNDERPASS, LED, TYPE C	EACH	24					24	
* X1400272	CONDUIT, 4" DIA., PVC COATED GALVANIZED STEEL	FOOT	2520						2520
* X1400269	ELECTRIC CABLE IN CONDUIT, NO. 14 6/C	FOOT	848					848	
* X1400270	ELECTRIC CABLE, AERIAL INSTALLATION, NO. 14 6/C	FOOT	900					900	
* X1400242	ELECTRIC CABLE, AERIAL INSTALLATION, NO. 19 50-PAIR	FOOT	700					700	
* X1400271	ELECTRIC CABLE, AERIAL INSTALLATION, NO. 2 2/C	FOOT	1600					1600	
* X1400241	FIBER OPTIC CABLE, AERIAL, 96 FIBERS, SINGLE MODE	FOOT	700					700	
* X1400240	FIBER OPTIC CABLE, IN CONDUIT, 96 FIBERS, SINGLE MODE	FOOT	300					300	
X1200159	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	1	1					
X1200160	CONNECTION TO EXISTING DRAINAGE STRUCTURE	EACH	2	2					
X0320085	MONITORING ADJACENT STRUCTURES	LSUM	1	1					

NOTE:
∅ TRAINEES AND TRAINEES TRAINING PROGRAM GRADUATE FUND NUMBER 0042

* DENOTES SPECIALTY ITEM
□ DENOTES NON-PARTICIPATING ITEM

REV 11-7-17

PARSONS BRINCKERHOFF

USER NAME = Kucharaki	DESIGNED - MMA	REVISED -
	DRAWN - MMA	REVISED -
PLOT SCALE = NO SCALE	CHECKED - RT	REVISED -
PLOT DATE = 7/13/2017	DATE - 07/14/2017	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 14 OF 14 SHEETS STA. TO STA.

F.A.I. RTE. 90/94	SECTION 2014-016R&B	COUNTY COOK	TOTAL SHEETS 378	SHEET NO. 178
			CONTRACT NO. 60X95	
[ILLINOIS] FED. AID PROJECT				

REV