

MODEL: Default
 FILE NAME: p:\p\hondrusse01\HDR_US_Central_01\Documents\11DOT\DOT_Phs II_Spec_Various TO's_199-13\DOT_PTB_199-13_TOT_18016.0_CAD_BIM6.2_WIP6.2.3_CADD_StreetRoadway\Summary of Quantities

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY URBAN	0006 ROADWAY 90% FED/ 10% STATE	0047 016-0074 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0075 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0076 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0077 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0078 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 016-0079 BRIDGE REHABILITATION 90% FED/ 10% STATE	0047 BRIDGE REHABILITATION 100% STATE
20200100	EARTH EXCAVATION	CU YD	12	12							
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45							
25100630	EROSION CONTROL BLANKET	SQ YD	2,380	2,380							
28000510	INLET FILTERS	EACH	6	6							
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	244				244				
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	6,653	6,653							
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8.7	8.7							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3,111	3,111							
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	490	490							
40605026	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 9.5, MIX "F", N80	TON	864	864							
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,239	1,239							
44200549	CLASS A PATCHES, TYPE I, 10 INCH	SQ YD	213	213							
44213000	PATCHING REINFORCEMENT	SQ YD	426	426							
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	213	213							
44213200	SAW CUTS	FOOT	2215	2215							
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	122	122							
44213204	TIE BARS 3/4"	EACH	1250	1250							
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	122	122							

LEGEND
 * - DENOTES SPECIALTY ITEM



USER NAME = RAZEVEDO	DESIGNED - NSA	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN - NSA	REVISED -
PLOT DATE = 6/13/2023	CHECKED - DJP	REVISED -
	DATE - 06/16/2023	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
 I-80**

SCALE: SHEET 1 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	2021-059-R5&BJR	COOK	185	3
			CONTRACT NO. 62N96	
(ILLINOIS) FED. AID PROJECT				