



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 30, 2023

SUBJECT FAP Route 873 (IL 149)
Project NHPP-JH89(002)
Section (28-5)K-1
Franklin County
Contract No. 78814

Item No. 95, November 17^h, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i-ii of the Table of Contents of the Special Provisions.
2. Revised page 18 of the Special Provisions.
3. Revised sheet 128 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
UTILITIES.....	1
TRAFFIC CONTROL PLAN	3
TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	4
STAGING PLAN.....	4
RAMP LANE RENTAL	5
LANE RENTAL.....	5
NIGHT TIME CONSTRUCTION	6
CHANGEABLE MESSAGE SIGNS	6
TEMPORARY RAMP (SPECIAL)	7
TEMPORARY PAVEMENT.....	7
NOTIFICATION PRIOR TO STARTING WORK.....	8
COMBINATION CONCRETE CURB AND GUTTER, TYPE M(SPECIAL)	8
SUBGRADE	8
AVAILABILITY OF ELECTRONIC FILES	8
STAMPED COLORED PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED) AND STAMPED COLORED PORTLAND CEMENT CONCRETE MEDIAN SURFACE, 4 INCH.....	9
FENCE (SPECIAL)	10
PROTECTIVE SHIELD	13
APPROACH SLAB REMOVAL	13
NIGHTTIME LANE RENTAL ON I-57 AT SN 028-0039	14
ISLAND REMOVAL.....	15
LANDSCAPING GRAVEL.....	15
INLET TYPE B, WITH SPECIAL FRAME AND GRATE.....	15
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	15
CHAIN LINK FENCE REMOVAL	17
DELINEATOR REMOVAL.....	17
PLUG EXISTING PIPE	17
PARAPET MOUNTED BRIDGE LIGHTING SYSTEM	18
DECK SLAB REPAIR.....	19
BRIDGE DECK MICROSILICA CONCRETE OVERLAY	24
PREFORMED BRIDGE JOINT SEAL.....	34
BAR SPLICERS	40

1

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) 41
 BLENDED FINELY DIVIDED MINERALS (BDE)..... 42
 CEMENT, TYPE IL (BDE)..... 43
 COMPENSABLE DELAY COSTS (BDE)..... 43
 DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 46
 FUEL COST ADJUSTMENT (BDE)..... 55
 PERFORMANCE GRADED ASPHALT BINDER (BDE)..... 57
 PORTLAND CEMENT CONCRETE (BDE) 62
 SEEDING (BDE) 62
 SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) 67
 SPEED DISPLAY TRAILER (BDE)..... 68
 STEEL COST ADJUSTMENT (BDE)..... 69
 SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 71
 SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 72
 SUBMISSION OF PAYROLL RECORDS (BDE) 72
 TRAFFIC SPOTTERS (BDE)..... 73
 TRAINING SPECIAL PROVISIONS (BDE) 75
 IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION..... 77
 VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 79
 WEEKLY DBE TRUCKING REPORTS (BDE)..... 80
 WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 80
 WORKING DAYS (BDE) 82
 PROJECT LABOR AGREEMENT 83
 STORM WATER POLLUTION PREVENTION PLAN..... 102

Basis of Payment: This work will be paid for at the contract unit price per CUBIC YARD for PLUG EXISTING PIPE.

PARAPET MOUNTED BRIDGE LIGHTING SYSTEM

Description: This work shall consist of furnishing and installing a parapet mounted bridge lighting system as shown on the plans and/or as specified by the Engineer. The parapet mounted bridge lighting system will be installed on the IL 149 over I-57 in West Frankfort. The work will include the design and installation of the bridge lighting system, power source(s), remote transformers, conduit, sensors, and all other components required to provide an operational parapet mounted bridge lighting system on the IL 149 Bridge over I-57. The Contractor will produce sealed shop drawings for approval of the Engineer prior to beginning work, and work shall commence upon approval by the Engineer. Work shall be performed in accordance with Sections 801, 806, 810-813, 816-817, and 821 of the Standard Specifications.

The parapet mounted bridge lighting system luminaires shall meet the following requirements.

- Manufacturer: BEGA or approved equivalent
- 33 020 LED recessed wall luminaires
- 30 LED white 3 W (4000K)
- Natural stainless-steel finish or equivalent.

The Contractor shall submit specification sheets for the luminaires to the Engineer for approval prior to ordering.

Method of Measurement: Parapet mounted bridge lighting system will be measured as a lump sum.

Basis of Payment: Parapet mounted bridge lighting system will be paid for at the contract unit price per LUMP SUM for PARAPET MOUNTED BRIDGE LIGHTING SYSTEM, which price shall include costs for all labor, materials, equipment, and incidentals necessary to perform the work.

1