



Notes

1. THE CONTRACTOR SHALL USE EXTREME CAUTION WORKING AROUND AND DEMOLISHING THE BUILDINGS AND STRUCTURES.
2. ALL BUILDINGS, STRUCTURES AND FOUNDATIONS SHALL BE REMOVED IN ACCORDANCE WITH SECTION 501 OF THE SPECIAL PROVISIONS. EACH SHALL BE REMOVED TO A MINIMUM DEPTH OF 3' BELOW THE FINAL GRADE.
3. CLEARING OF TREES SHALL BE KEPT TO A MINIMUM AND SHALL BE SIGNIFICANTLY LESS THAN SHOWN BY THE CONSTRUCTION LIMITS. ACCESS TO ISOLATED AREAS THROUGHOUT THE SITE SHALL BE BY EXISTING PATHWAYS OR BY CLEARED AREAS AS SHORT AND AS NARROW AS POSSIBLE.

	EXISTING CONTOUR
	PROPOSED CONTOUR
	PROPOSED RUBBLE PIT CONTOUR
	PROPOSED CONSTRUCTION LIMITS
	BASELINE FOR CROSS SECTIONS
	TREE LINE
	SECTION LINE
	EDGE OF WATER
	CONTROL POINT
	BORING LOCATION (APPROX.)
	EXISTING STRUCTURE
	PROPOSED EXCELSIOR BLANKET (8' WIDTH)

Legend

Bell & Zoller #2 Mine

