



**Notes**

1. THE CONTRACTOR SHALL USE CAUTION WHEN WORKING WITH EQUIPMENT ON THE EXPOSED SLURRY AS IT IS UNSTABLE MATERIAL ESPECIALLY DURING WET PERIODS. THE DEPTH OF SLURRY IS AT LEAST 5 FEET (PER THREE HAND-AUGERED BORINGS).
2. ALL DISTURBED AREAS AND ALL ROADS WITHIN THE CONSTRUCTION LIMITS (EXCEPT THE MAIN ACCESS ROAD FROM IL RTE 149) SHALL BE DIRECTLY SEEDED IN ACCORDANCE WITH SECTION 250 OF THE SPECIAL PROVISIONS. ALL SEEDED AND MULCHED AREAS SHALL BE MEASURED IN ACRES FOR PAYMENT.

**Legend**

	EXISTING CONTOUR
	PROPOSED CONTOUR
	PROPOSED RUBBLE PIT CONTOUR
	PROPOSED CONSTRUCTION LIMITS
	BASILINE FOR CROSS SECTIONS
	TREE LINE
	SECTION LINE
	EDGE OF WATER
	CONTROL POINT
	BORING LOCATION (APPROX.)
	EXISTING STRUCTURE
	PROPOSED EXCELSIOR BLANKET (8' WIDTH)

