

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94		COOK	631	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(2425 & 2626) R-2		CONTRACT NO. 62111		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	1-80 **	RAILROAD, BURNHAM, 175TH ST., BERNICE **	BRIDGE ** 016-2791	BRIDGE ** 016-2792	RETAINING WALLS **	SURVEILLANCE **	LANSING ****	SIGNING **					
				J000-2A 60	I000-2A	X271-2A	X281-2A	Y007	Y032-1F	I000-2A	Y002-IC					
M5510060	STORM SEWER REMOVAL 600MM	METER	60	60												
M5510095	STORM SEWER REMOVAL 1200MM	METER	261.5	54.5	207											
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	547					547								
M6010610	PIPE UNDERDRAINS 150MM	METER	4399	4399												
M6011105	PIPE UNDERDRAINS FOR STRUCTURES 150MM	METER	103					103								
M6020105	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	16	3	8					5						
M6020140	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 8 GRATE	EACH	6		6											
M6020185	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 24 FRAME AND GRATE	EACH	12		12											
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3		1					2						
M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2											
M6022010	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2											
M6060070	CONCRETE CURB, TYPE B	METER	14		14											
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	665		401					264						
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	756		756											
M6063630	CONCRETE MEDIAN SURFACE, 150MM (SPECIAL)	SQ M	1132	1132												
M6320030	GUARDRAIL REMOVAL	METER	73	73												
M6370155	CONCRETE BARRIER, SINGLE FACE, 815 MM HEIGHT	METER	742	742												
M6370175	CONCRETE BARRIER, SINGLE FACE, 1065 MM HEIGHT	METER	58	58												
M6370255	CONCRETE BARRIER, DOUBLE FACE, 815MM HEIGHT	METER	435	435												
M6370275	CONCRETE BARRIER, DOUBLE FACE, 1065 MM HEIGHT	METER	2101	2101												
M6370805	CONCRETE BARRIER TRANSITION	METER	39	39												
M6371050	BARRIER BASE	METER	3850	3850												
00 M6380600	MODULAR GLARE SCREEN SYSTEM	METER	364.7	304.7												
M6420015	SHOULDER RUMBLE STRIP	METER	13881	13881												
M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	13		13											
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	2401	2401												
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	11426	10678	748											
M7030260	TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	65	65												
M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	18	18												
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	12915	12915												
M7030530	PAVEMENT MARKING TAPE, TYPE III 125MM	METER	1092	1092												
M7030550	PAVEMENT MARKING TAPE, TYPE III 200MM	METER	1280	1280												
M7030560	PAVEMENT MARKING TAPE, TYPE III 300MM	METER	342	342												
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	1886	1886												
M7040100	TEMPORARY CONCRETE BARRIER	METER	1277	903	374											
M7200100	SIGN PANEL - TYPE 1	SQ M	30								30					
M7200200	SIGN PANEL - TYPE 2	SQ M	13.7								13.7					
M7200300	SIGN PANEL - TYPE 3	SQ M	155.2								155.2					

*SPECIALTY ITEMS
 **90% FEDERAL
 10% STATE
 ***50% STATE
 50% VILLAGE OF LANSING
 ****100% VILLAGE OF LANSING
 *****100% CITY OF CHICAGO
 HEIGHTS
 **90% FEDERAL
 5% STATE
 5% VILLAGE OF LANSING

S:\017002\A.DGN, ..\S017002\A.DGN, ..\AB99002\A.DGN
 9-14-2005, 13:08:38
 F:\DOCUMENT\937501\CVL\UDN\S017002\A.DGN
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63
 STANUR, J

00 SFTY-2A 90% FED./10% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY)
 EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION
 COOK COUNTY

**SUMMARY OF QUANTITIES
 IV**

SCALE: NONE
 DATE: 9/13/05

DRAWN BY: SNM
 CHECKED BY: KC

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS