

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	631	10
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (2425 & 2626) R-2 CONTRACT NO. 62111

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	1-80	RAILROAD, BURNHAM, 175TH ST., BERNICE	BRIDGE ** 016-2791	BRIDGE ** 016-2792	RETAINING WALLS **	SURVEILLANCE **	LANSING ****	TRAFFIC SIGNALS **
				J000-2A	I000-2A	X271-2A	X281-2A	Y007	Y032-1F	I000-2A	Y031-1F
MX033276	TEMPORARY SOIL RETENTION SYSTEM	SQ M	124				124				
MX033290	SEDIMENT CONTROL, SILT FENCE	METER	612	265	347						
MX033291	SEDIMENT CONTROL, SILT FENCE, MAINTENANCE	METER	612	265	347						
MX033292	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ M	1622	811	811						
MX033303	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ M	406	203	203						
MX355150	BITUMINOUS BASE COURSE SUPERPAVE, 150MM	SQ M	143		143						
MX355200	BITUMINOUS BASE COURSE SUPERPAVE, 200MM	SQ M	76		76						
MX406012	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	M TON	1589.1	1253.3	26.1				309.7		
MX407380	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 230MM	SQ M	4242		2644				1598		
MX407450	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 300MM	SQ M	5665		5665						
MX482280	BITUMINOUS SHOULDERS SUPERPAVE 150MM	SQ M	250	250							
MX512015	TEMPORARY SHEET PILING REMOVAL	SQ M	3434	3274		160					
MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	5339	5339							
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	10787		9061				1726		
MZ031106	TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ M	510				510				
MZ047300	PROTECTIVE SHIELD	SQ M	1164			1164					
MZ065755	SLOTTED DRAIN 300MM WITH VARIABLE SLOT HEIGHT	METER	96.9	96.9							
X0322916	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	EACH	10		10						
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	2	1	1						
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	145	98	47						
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	12	11	1						
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	8	8							
X0324587	NOISE ABATEMENT WALL ANCHOR ROD ASSEMBLY	EACH	45		21			24			
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	489	489							
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	20		20						
X6020166	DRAINAGE STRUCTURES, TYPE 1 SPECIAL WITH TWO TYPE 20 FRAME AND GRATES	EACH	14	14							
X6020167	DRAINAGE STRUCTURES, TYPE 2 SPECIAL WITH TWO TYPE 22 FRAME AND GRATES	EACH	1	1							
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1							
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	240	240							
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	10	10							
X8800020	SIGNAL HEAD ,LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4								4
X8800037	SIGNAL HEAD ,LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2								2
X8800038	SIGNAL HEAD ,LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2								2
X8800040	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2								2
X8800045	SIGNAL HEAD ,LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2								2
X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	8								8
XX001452	CONCRETE MASONRY BULKHEAD	EACH	11	5	6						
Z0002600	BAR SPLICERS	EACH	1506			1242	264				

*SPECIALTY ITEMS
 **90% FEDERAL
 10% STATE
 ***50% STATE
 50% VILLAGE OF LANSING
 ****100% VILLAGE OF LANSING
 *****100% CITY OF CHICAGO
 HEIGHTS
 #90% FEDERAL
 5% STATE
 5% VILLAGE OF LANSING

S:\PROJECTS\94\940005\1488\43 1\DOCUMENT\93750\CON\CIVIL\WORK\SO100702\ADON
 9-14-2005 14:48:43 1\DOCUMENT\93750\CON\CIVIL\WORK\SO100702\ADON
 1,2,3,4,5,6,7,8,9,10,11,12,13,14,15,16,17,18,19,20,21,22,23,24,25,26,27,28,29,30,31,32,33,34,35,36,37,38,39,40,41,42,43,44,45,46,47,48,49,50,51,52,53,54,55,56,57,58,59,60,61,62,63

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY)
 EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION
 COOK COUNTY

SUMMARY OF QUANTITIES VI

SCALE: NONE
 DATE: 9/13/05

DRAWN BY: SNM
 CHECKED BY: KC

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS