F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	* 2003-028F	COOK	419	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62580

SHEET NUMBER	STATION	TO STATION	MODULAR GLARE SCREEN SYSTEM (FOOT)
MOT-04 EB I-94/90	87+94	99+94	1,060
MOT-05 EB I-94/90	99+94	111+94	1,200
MOT-06 EB I-94/90	111+94	125+39	1,200
MOT-08 EB I-94/90	125+39	137+39	1,200
MOT-09 EB I-94/90	137+39	149+39	1,200
MOT-10 EB I-94/90	149+39	161+39	1,200
MOT-11 EB I-94/90	161+39	173+25	1,200
MOT-12 EB I-94/90	173+25	184+51	1,200
MOT-13 EB I-94/90	184+51	196+51	470
		TOTAL	9,930

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING-TAPE, TYPE III LETTERS AND SYMBOLS (SQ FT)
MOT-20 WB I-94/90	ARROW	2626+00	2638+00	15.6
	AND ONLY			20.8
MOT-21 WB I-94/90	ARROW	2638+00	75+94	15.6
	AND ONLY			20.8
			TOTAL	73

SHEET NUMBER	STATION	TO STATION	TEMPORARY PAVEMENT MARKING-LINE 6" (FOOT)
MOT-04 WB I-94/90	87+94	99+94	1,120
MOT-05 WB I-94/90	99+94	111+94	1,200
MOT-06 WB I-94/90	111+94	125+39	1,200
RAMP			580
MOT-08 WB I-94/90	125+39	137+39	1,200
RAMP			1,150
MOT-09 WB I-94/90	137+39	149+39	1,000
RAMP			1,180
MOT-17 RAMP	111+94	125+39	580
MOT-19 RAMP	125+39	137+39	10
MOT-23 WB I-94/90	87+94	99+94	850
MOT-24 WB I-94/90	99+94	111+94	1,200
MOT-25 WB I-94/90	111+94	125+39	1,200
MOT-27 WB I-94/90	125+39	137+39	1,100
MOT-28 WB I-94/90	137+39	149+39	1,200
MOT-29 WB I-94/90	149+39	161+39	380
MOT-30 WB I-94/90	161+39	173+25	1,200
MOT-31 WB I-94/90	173+25	184+51	1,200
MOT-39 RAMP	99+94	111+94	100
MOT-40 RAMP	111+94	125+39	130
MOT-42 WB I-94/90	125+39	137+39	350
RAMP			760
MOT-43 RAMP	137+39	149+39	198
MOT-44 WB I-94/90	149+39	161+39	623
		TOTAL	19,711

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TAPE, TYPE III 4" (FOOT)
MOT-20 WB I-94/90	WHITE	2626+00	2638+00	845
MOT-21 WB I-94/90	WHITE	2638+00	75+94	1,355
	YELLOW			943
MOT-22 WB I-94/90	WHITE	75+94	87+94	1,200
	YELLOW			1,365
MOT-23 WB I-94/90	WHITE	87+94	99+94	1,200
RAMP	YELLOW			1,200
MOT-24 WB I-94/90	WHITE	99+94	111+94	1,200
	YELLOW			1,200
MOT-25 & 26 WB I-94/90	WHITE	111+94	125+39	1,490
	YELLOW			1,200
	6'S-2'D			63
MOT-27 WB I-94/90	WHITE	125+39	137+39	1,996
	YELLOW			1,965
	6'S-2'D			38
MOT-28 WB I-94/90	WHITE	137+39	149+39	2,390
	YELLOW			2,390
MOT-29 WB I-94/90	WHITE	149+39	161+39	712
	YELLOW			1,430
	6'S-2'D			83
MOT-30 WB I-94/90	WHITE	161+39	173+25	1,200
	YELLOW			1,200
MOT-31 WB I-94/90	WHITE	173+25	184+51	1,107
	YELLOW			1,200
	6'S-2'D			25
MOT-32 WB I-94/90	WHITE	184+51	196+51	143
	YELLOW			240
	6'S-2'D			40
MOT-39 WB I-94/90	6'S-2'D	99+94	111+94	40

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	PAVEMENT MARKING TAPE, TYPE III 4" (FOOT)
MOT-40 WB I-94/90	YELLOW	111+94	125+39	288
MOT-42 WB I-94/90	WHITE	125+39	137+39	360
	YELLOW			765
MOT-43 WB I-94/90	WHITE	137+39	149+39	430
	YELLOW			430
	6'S-2'D			21
MOT-44 WB I-94/90	WHITE	149+39	161+39	982
	6'S-2'D			56
MOT-45 WB I-94/90	WHITE	161+39	173+25	130
MOT-46 WB I-94/90	WHITE	173+25	184+51	398
	YELLOW			473
	6'S-2'D			58
MOT-47 WB I-94/90	YELLOW	184+51	196+51	180
			TOTAL	34,030

CSCH-01

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
NB DAN RYAN ELEVATED BRIDGE
REPAIR FROM 15TH TO 28TH STREETS
CIVIL SCHEDULES

SCALE: =NTS DRAWN BY: RA
DATE: 8/12/2005 CHECKED BY: RS

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

N:\660\cad\CH\13\SHEETS\660_13CPLSCH01.dgn 8/11/2005 3:39:29 PM