

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	WORKZONE PAVEMENT MARKING REMOVAL (SQ FT)
MOT-19	4" WHITE 4" YELLOW	125+39	137+39	100 100
MOT-20	4" WHITE 5" 10D-30S 8" SOLID 12" SOLID	2626+00	2638+00	188 59 415 50
MOT-21	4" WHITE 4" YELLOW 12" SOLID	2638+00	75+94	335 295 80
MOT-25	4" YELLOW	111+94	125+39	193
MOT-27	4" WHITE 4" YELLOW 5" 10D-30S 8" SOLID	125+39	137+39	260 363 31 200
MOT-29	4" WHITE 4" 2D-6S 5" 10D-30S	149+39	161+39	193 45 50
MOT-31	4" YELLOW	173+25	184+51	40
MOT-32	4" YELLOW 5" 10D-30S 8" SOLID 12" SOLID	184+51	196+51	118 76 566 218
MOT-33	4" YELLOW 5" 10D-30S 8" SOLID 12" SOLID	196+51	208+51	369 78 376 72
MOT-34	4" YELLOW 8" SOLID 8" 3D-12S LETTERS & SYMBOLS	208+51	-	93 187 49 73
MOT-35	4" WHITE 4" YELLOW 5" 10D-30S 8" SOLID	2626+00	2638+00	282 276 130 548

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	WORKZONE PAVEMENT MARKING REMOVAL (SQ FT)
MOT-36	8" 2D-6S LETTERS & SYMBOLS	2638+00	75+94	29 73
MOT-37	4" WHITE 4" YELLOW 5" 10D-30S 8" SOLID 12" SOLID LETTERS & SYMBOLS	75+94	87+94	632 259 172 1,327 128 36
MOT-38	4" WHITE 4" YELLOW 5" 10D-30S	87+94	99+94	800 800 125 279 96
MOT-39	4" WHITE 4" YELLOW 5" 10D-30S	99+94	111+94	800 1,038 323
MOT-40	4" WHITE 4" YELLOW 4" 2D-6S 5" 10D-30S 8" SOLID 12" SOLID	111+94	125+39	954 1,200 38 375 1,177 448
MOT-42	4" WHITE 4" YELLOW 4" 2D-6S 5" 10D-30S 8" SOLID	125+39	137+39	1,577 1,580 21 375 580 140
MOT-43	4" WHITE 4" YELLOW 4" 2D-6S 5" 10D-30S 8" SOLID 12" SOLID	137+39	149+39	1,390 1,580 32 375 333
MOT-44	4" WHITE 4" YELLOW 4" 2D-6S 5" 10D-30S 8" SOLID	149+39	161+39	1,550 1,623 7 375 777 100
MOT-45	4" WHITE 4" YELLOW 5" 10D-30S	161+39	173+25	897 1,200 69 319 584
MOT-47	4" WHITE 4" YELLOW 4" 2D-6S 5" 10D-30S 8" SOLID	161+39	173+25	843 1,200 218
MOT-46	4" WHITE 4" YELLOW 4" 2D-6S 5" 10D-30S 8" SOLID 12" SOLID	173+25	184+51	1,115 1,360 27 492 1,441 771
MOT-47	4" WHITE 4" YELLOW 4" 2D-6S 5" 10D-30S 8" SOLID	184+51	196+51	294 741 13 338 2,535

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	WORKZONE PAVEMENT MARKING REMOVAL (SQ FT)
	12" SOLID			504
TOTAL				44,991

SHEET NUMBER	DESCRIPTION	STATION	TO STATION	EPOXY PAVEMENT MARKING-LETTERS AND SYMBOLS (SQ FT)
MOT-01	WB I-94/90 ARROW AND ONLY (1)	2626+00	2638+00	15.6 20.8
MOT-15	WB I-94/90 ARROW AND ONLY (2)	208+51	-	31.2 41.6
CPM-01	WB I-94/90 ARROW AND ONLY (1)	2626+00	2638+00	15.6 20.8
CPM-04	WB I-94/90 ARROW AND ONLY (2)	87+94	99+94	31.2 41.6
CPM-05	WB I-94/90 ARROW AND ONLY (1)	99+94	111+94	15.6 20.8
CPM-10	EB I-94/90 ARROW AND ONLY (1)	149+39	161+39	15.6 20.8
CPM-11	EB I-94/90 ARROW AND ONLY (2)	161+39	173+25	31.2 41.6
CPM-12	WB I-94/90 ARROW AND ONLY (1)	173+25	184+51	15.6 20.8
TOTAL				400

SHEET NUMBER	STATION	TO STATION	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)
MOT-17 RAMP	111+94	125+39	580
MOT-19 RAMP	125+39	137+39	140
MOT-23 WB I-94/90	87+94	99+94	1,120
MOT-24 WB I-94/90	99+94	111+94	1,200
MOT-25 WB I-94/90	111+94	125+39	1,200
MOT-27 WB I-94/90 RAMP	125+39	137+39	1,270 650
MOT-28 WB I-94/90 RAMP	137+39	149+39	1,200 1,180
MOT-29 WB I-94/90	149+39	161+39	958
MOT-30 WB I-94/90	161+39	173+25	1,200
MOT-31 WB I-94/90	173+25	184+51	1,200
MOT-39 WB I-94/90	99+94	111+94	310
MOT-40 RAMP	111+94	125+39	130
MOT-42 WB I-94/90 RAMP	125+39	137+39	350 760
MOT-43 RAMP	137+39	149+39	650
MOT-44 WB I-94/90	149+39	161+39	1,125
MOT-45 WB I-94/90	161+39	173+25	120
TOTAL			15,343

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com

REVISIONS	
NAME	DATE
ADDENDUM 1	9/6/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
NB DAN RYAN ELEVATED BRIDGE
REPAIR FROM 15TH TO 28TH STREETS
CIVIL SCHEDULES

SCALE: =NTS
DATE: 8/12/2005

DRAWN BY: RA
CHECKED BY: RS